

**STORM 2006
THORNTON STREET IMPROVEMENTS RE-BID
BID NO. 2007 - 196**

SCOPE OF WORK

Base Bid:

As a part of the Storm 2006 Project, the Thornton Street Improvement consists on enhancing the street condition of Thornton Street that runs from Lindbergh to Country Club Road.

This will require establishing traffic control and erosion control devices. Selective demolition of the existing structures running the span of the 40 feet Right of Way, which includes, but not limited to, demolition of the street, several residential driveways (concrete, asphalt, and brick) and walkways. Demolition will also include the removal of a Rock Stemwall and an existing tree(s) in the section near Country Club Road.

The improvements will include the construction of the 20 ft wide roadway with adjacent sidewalks, including header curbs and accessible ramps with truncated domes. Construction will also include replacing the demolished concrete, asphalt, and brick driveways and sidewalks, along with adjusting the affected pedestrian gates.

Alternate 1:

Lime Treated Subgrade will be conducted by scarifying the existing subgrade and blending in Lime at the Geotech recommended percentage.

Alternate 2:

Installation of BX 1100 Tensar Geogrid for the areas under the pavement and sidewalk.

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: THORNTON STREET IMPROVEMENTS " REBID "
 BID DATE: JUNE 13, 2007

BID NO.: 2007- 196
 Dept: Street

				ALLEN CONCRETE, INC. EL PASO, TEXAS		C. F. JORDAN, L.P. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS		J. A. R. CONCRETE, INC. EL PASO, TEXAS		SILVERTON CONSTRUCTION, CO. INC. EL PASO, TEXAS	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID I UNIT PRICE SCHEDULE													
1	1	LS	BONDING, INSURANCE, ETC.	\$11,699.05	\$11,699.05	\$18,000.00	\$18,000.00	\$5,000.00	\$5,000.00	\$15,500.00	\$15,500.00	\$7,000.00	\$7,000.00
2	1	LS	MOBILIZATION	\$48,000.00	\$48,000.00	\$54,000.00	\$54,000.00	\$15,000.00	\$15,000.00	\$50,000.00	\$50,000.00	\$12,000.00	\$12,000.00
3	4,300	SF	DEMOLITION AND REMOVAL OF EXISTING PAVEMENT	\$6.50	\$27,950.00	\$2.00	\$8,600.00	\$4.00	\$17,200.00	\$3.10	\$13,330.00	\$8.00	\$34,400.00
4	1,925	SY	DEMOLITION AND REMOVAL OF EXISTING CONCRETE DRIVEWAYS	\$9.50	\$18,287.50	\$2.00	\$3,850.00	\$7.00	\$13,475.00	\$4.00	\$7,700.00	\$4.00	\$7,700.00
5	200	SF	DEMOLITION AND REMOVAL OF EXISTING BRICK DRIVEWAYS	\$9.00	\$1,800.00	\$5.00	\$1,000.00	\$7.00	\$1,400.00	\$10.00	\$2,000.00	\$4.00	\$800.00
6	85	SY	DEMOLITION AND REMOVAL OF EXISTING ASPHALT DRIVEWAYS	\$22.00	\$1,870.00	\$4.00	\$340.00	\$5.00	\$425.00	\$15.00	\$1,275.00	\$4.00	\$340.00
7	61	LF	DEMOLITION AND REMOVAL OF EXISTING ROCK STEMWALL	\$22.00	\$1,342.00	\$10.00	\$610.00	\$25.00	\$1,525.00	\$21.00	\$1,281.00	\$5.00	\$305.00
8	1	EACH	DEMOLITION AND REMOVAL OF EXISTING TREE (WITHIN ROW)	\$650.00	\$650.00	\$1,500.00	\$1,500.00	\$1,000.00	\$1,000.00	\$500.00	\$500.00	\$1,000.00	\$1,000.00
9	2	EACH	DEMOLITION OF EXISTING SIGNS	\$150.00	\$300.00	\$300.00	\$600.00	\$200.00	\$400.00	\$100.00	\$200.00	\$150.00	\$300.00
10	1,470	CY	PROPOSED: LIGHT DUTY PAVEMENT (HMAC, BASE)	\$18.50	\$27,195.00	\$18.00	\$26,460.00	\$18.00	\$26,460.00	\$15.50	\$22,785.00	\$15.00	\$22,050.00

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: THORNTON STREET IMPROVEMENTS "REBID"
 BID DATE: JUNE 13, 2007

BID NO.: 2007- 196
 Dept: Street

	ALLEN CONCRETE, INC. EL PASO, TEXAS	C. F. JORDAN, L.P. EL PASO, TEXAS	DAN WILLIAMS COMPANY EL PASO, TEXAS	J. A. R. CONCRETE, INC. EL PASO, TEXAS	SILVERTON CONSTRUCTION, CO. INC. EL PASO, TEXAS
--	--	--------------------------------------	--	---	---

ITEM #	EST. QTY	UNITS	DESCRIPTION	ALLEN CONCRETE, INC.		C. F. JORDAN, L.P.		DAN WILLIAMS COMPANY		J. A. R. CONCRETE, INC.		SILVERTON CONSTRUCTION, CO. INC.	
				UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID UNIT PRICE SCHEDULE													
11	2,230	SY	PROPOSED: HEAVY DUTY PAVEMENT (HMAC, BASE)	\$22.50	\$50,175.00	\$21.00	\$46,830.00	\$20.00	\$44,600.00	\$16.00	\$35,680.00	\$17.00	\$37,910.00
12	1,730	CY	SCARIFYING OF EXISTING SUBGRADE	\$22.50	\$38,925.00	\$5.00	\$8,650.00	\$5.00	\$8,650.00	\$12.50	\$21,625.00	\$8.00	\$13,840.00
13	1,400	CY	PROPOSED: IMPORT FILL MATERIALS	\$19.00	\$26,600.00	\$20.00	\$28,000.00	\$23.00	\$32,200.00	\$20.00	\$28,000.00	\$14.00	\$19,600.00
14	11,925	SF	PROPOSED: SIDEWALK	\$3.25	\$38,756.25	\$4.00	\$47,700.00	\$4.50	\$53,662.50	\$4.00	\$47,700.00	\$4.00	\$47,700.00
15	2,960	PERCH	PROPOSED: ROCK STEMWALL	\$7.50	\$22,200.00	\$13.00	\$38,480.00	\$12.00	\$35,520.00	\$8.00	\$23,680.00	\$7.00	\$20,720.00
16	5	EACH	PEDESTRIAN GATE ADJUSTMENTS	\$220.00	\$1,100.00	\$220.00	\$1,100.00	\$150.00	\$750.00	\$185.00	\$925.00	\$200.00	\$1,000.00
17	2	SF	PROPOSED: CONCRETE DRIVEWAYS	\$175.00	\$350.00	\$500.00	\$1,000.00	\$800.00	\$1,600.00	\$600.00	\$1,200.00	\$300.00	\$600.00
18	3,150	SF	PROPOSED: BRICK DRIVEWAYS	\$4.10	\$12,915.00	\$6.00	\$18,900.00	\$7.00	\$22,050.00	\$6.00	\$18,900.00	\$6.00	\$18,900.00
19	510	SY	PROPOSED: ASPHALT DRIVEWAYS	\$9.50	\$4,845.00	\$8.00	\$4,080.00	\$15.00	\$7,650.00	\$9.50	\$4,845.00	\$9.00	\$4,590.00
20	165	EACH	PROPOSED: TRUNCATED DOMES	\$22.50	\$3,712.50	\$31.00	\$5,115.00	\$15.00	\$2,475.00	\$28.00	\$4,620.00	\$20.00	\$3,300.00
21	10	EACH	NEW STOP SIGN AND POLE MOUNT	\$750.00	\$7,500.00	\$500.00	\$5,000.00	\$1,500.00	\$15,000.00	\$470.00	\$4,700.00	\$400.00	\$4,000.00

APPROVED BY: *MWP*

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: THORNTON STREET IMPROVEMENTS "REBID "
 BID DATE: JUNE 13, 2007

BID NO.: 2007- 196
 Dept: Street

				ALLEN CONCRETE, INC. EL PASO, TEXAS		C. F. JORDAN, L.P. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS		J. A. R. CONCRETE, INC. EL PASO, TEXAS		SILVERTON CONSTRUCTION, CO. INC. EL PASO, TEXAS	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID 1 UNIT PRICE SCHEDULE													
22	2	EACH	NEW NO TRUCK SIGN AND POLE MOUNT	\$250.00	\$500.00	\$700.00	\$1,400.00	\$300.00	\$600.00	\$315.00	\$630.00	\$300.00	\$600.00
23	1	EACH	NEW STREET SIGNS	\$650.00	\$650.00	\$700.00	\$700.00	\$300.00	\$300.00	\$350.00	\$350.00	\$300.00	\$300.00
24	4	LF	PAVEMENT STRIPING (CENTER LINE)	\$1,475.00	\$5,900.00	\$600.00	\$2,400.00	\$100.00	\$400.00	\$380.00	\$1,520.00	\$300.00	\$1,200.00
25	3,100	EACH	PAVEMENT STRIPING (STOP BAR/PEDESTRIAN CROSSING)	\$1.75	\$5,425.00	\$1.00	\$3,100.00	\$3.50	\$10,850.00	\$1.55	\$4,805.00	\$1.00	\$3,100.00
26	2	EACH	PAVEMENT STRIPING (STOP BAR / PEDESTRIAN CROSSING)	\$1,200.00	\$2,400.00	\$1,200.00	\$2,400.00	\$800.00	\$1,600.00	\$615.00	\$1,230.00	\$800.00	\$1,600.00
27	1	LS	TRAFFIC CONTROL (BARRICADES, SIGNS, TRAFFIC HANDLING)	\$65,000.00	\$65,000.00	\$9,500.00	\$9,500.00	\$25,000.00	\$25,000.00	\$35,000.00	\$35,000.00	\$10,000.00	\$10,000.00
28	1	LS	SWPP MEASURES (SILT FENCE, MAINTENANCE, ETC.)	\$15,000.00	\$15,000.00	\$17,000.00	\$17,000.00	\$24,000.00	\$24,000.00	\$15,000.00	\$15,000.00	\$15,000.00	\$15,000.00
29	2	EACH	SEWER MAN HOLE AJUSTMENTS	\$450.00	\$900.00	\$800.00	\$1,600.00	\$800.00	\$1,600.00	\$500.00	\$1,000.00	\$300.00	\$600.00

APPROVED BY: *MUP*

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: THORNTON STREET IMPROVEMENTS " REBID "
 BID DATE: JUNE 13, 2007

BID NO.: 2007-196
 Dept: Street

				ALLEN CONCRETE, INC. EL PASO, TEXAS		C. F. JORDAN, L.P. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS		J. A. R. CONCRETE, INC. EL PASO, TEXAS		SILVERTON CONSTRUCTION, CO. INC. EL PASO, TEXAS	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID I UNIT PRICE SCHEDULE													
30	9	EACH	WATER VALVE BOX ADJUSTMENTS	\$225.00	\$2,025.00	\$450.00	\$4,050.00	\$500.00	\$4,500.00	\$350.00	\$3,150.00	\$300.00	\$2,700.00
31	2	EACH	CABLE BOX ADJUSTMENTS	\$325.00	\$650.00	\$600.00	\$1,200.00	\$800.00	\$1,600.00	\$950.00	\$1,900.00	\$300.00	\$600.00
32	1	EACH	TELEPHONE BOX ADJUSTMENT	\$375.00	\$375.00	\$600.00	\$600.00	\$800.00	\$800.00	\$950.00	\$950.00	\$300.00	\$300.00
SUM TOTAL BASE BID I (ITEM NOS. 1 - 32)					\$444,997.30		\$363,765.00		\$377,292.50		\$371,981.00		\$294,055.00
ALTERNATES I UNIT PRICE SCHEDULE													
1	70	CY	SUBGRADE LIME TREATMENT	\$95.00	\$6,650.00	\$680.00	\$47,600.00	\$200.00	\$14,000.00	\$550.00	\$38,500.00	\$260.00	\$18,200.00
ALTERNATE # 1 SUM TOTAL					\$6,650.00		\$47,600.00		\$14,000.00		\$38,500.00		\$18,200.00
ALTERNATES II UNIT PRICE SCHEDULE													
1	3,445	SY	BX 1100 TENSAR GEOGRID	\$5.75	\$19,808.75	\$4.00	\$13,780.00	\$5.00	\$17,225.00	\$5.50	\$18,947.50	\$7.00	\$24,115.00
SUM TOTAL ALTERNATE # II					\$19,808.75		\$13,780.00		\$17,225.00		\$18,947.50		\$24,115.00
BID BOND SUBMITTED				YES		YES		YES		YES		YES	
AMENDMENTS ACKNOWLEDGED				YES		YES		YES		YES		YES	

THIS AGREEMENT, made and between THE CITY OF EL PASO, County of El Paso, Texas, hereinafter called "Owner", acting herein through its City Manager, Joyce Wilson and Silverton Construction Co., Inc. a corporation, of El Paso, COUNTY OF El Paso and STATE OF Texas, hereinafter called "Contractor".

WITNESSETH: That for and in consideration of the payments and agreements hereinafter mentioned, to be made and performed by the Owner, the Contractor hereby agrees with the Owner to commence and complete the construction described as follows:

**Storm 2006: Thornton Street Improvements Re-Bid
Solicitation No. 2007-196**

Hereinafter called the "Project", for the sum of Three hundred twelve thousand, two hundred fifty five Dollars and .00 Cents (\$ 312,255.00), and all extra work in connection therewith, under the terms as stated in the contract documents; and at Contractor(s) own proper cost and expense to furnish all the materials, supplies, machinery, equipment, tools, superintendence, labor, insurance and other accessories and services necessary to complete the said Project, in accordance with the conditions and prices stated in the Proposal, the General Conditions, Supplemental General Conditions and Special Conditions of the Contract, the plans, which include all maps, plats, blueprints and other drawings and printed or written explanatory matter thereof, the specifications and contract documents thereof as furnished by the CITY ENGINEER or designated representative, and as enumerated in Paragraph 1.5 of the General Conditions, all of which are made a part hereof and collectively evidence and constitute the Contract.

The Contractor hereby agrees to commence work under this Contract on a date to be specified in a written "Notice to Proceed" from the Owner, and to substantially complete the project within One Hundred Twenty (120) consecutive calendar days thereafter. The Contractor further agrees to pay, as liquidated damages, the sum of Three hundred Dollars (\$300.00) for each consecutive calendar day thereafter, as hereinafter provided in Paragraph 6.8 of the General Conditions.

The unit price quantities of this contract are estimated.

Base Bid I \$294,055.00 Alternate I \$18,200.00

CONTRACT

IN WITNESS, WHEREOF, the parties to these presents have executed this Contract on the 18 day of JUNE, 2007 in two (2) counterparts, each of which shall be deemed an original, in the year and day first above mentioned.

OWNER - CITY OF EL PASO

by Joyce Wilson
City Manager Joyce Wilson

APPROVED AS TO FORM:

[Signature]
Assistant City Attorney

Contractor: Silverton Construction Co., Inc.

by [Signature]

PROCESSED BY FINANCIAL SERVICES:

[Signature]
CEO, Financial Services

MIKE WHITNEY, PRESIDENT
Typed Name & Title

P.O. BOX 12629, EL PASO, TEXAS 79913
Address, City, State, Zip Code

915-581-1138 915-833-8766
Telephone Number Fax Number

PROCESSED BY ENGINEERING:

[Signature]
City Engineer

If the Contractor be a corporation, the following certificate should be executed:

I, ROBERT F. FERRELL, certify that I am the
Secretary of the corporation named as Bidder,
hereinabove; and that MIKE WHITNEY, who signed the foregoing
Contract on behalf of the Bidder was then PRESIDENT of said
corporation; that said proposal was duly signed for and in behalf of said corporation by authority
of its governing body, and is within the scope of its corporate powers.

[Signature]
CORPORATE SECRETARY SIGNATURE AND CORPORATE SEAL

City of El Paso

Scope of Work

Storm 2006: High Ridge & Bear Ridge Channel Drainage Improvements Solicitation No. 2007-209

BASE BID : (Unit Price Schedule)

High Ridge Channel at Redd Road Location: Demolition and removal of existing channel features damaged by "Storm 2006" include existing concrete sidewalk, concrete driveway, concrete curb and gutter, chain link fence, landscape rock wall and concrete embankment protection slabs. Improvements consist of furnishing and installing new concrete sidewalk (7 SY), concrete driveway (17 SY), concrete curb and gutter (30 LF), chain link fence (30 LF), landscape rock wall (7 perches) and concrete embankment protection slabs (46 SY).

6813 Pasa Tiempo Circle: The existing rock wall along the rear property line damaged by the events of "Storm 2006" will be demolished and removed in its entirety and replaced with a proposed structural hydrostatic wall. The proposed hydrostatic wall will range in height from 7' (maximum) to 6' (average) and finally taper down to a minimum height of 2'. The proposed structural hydrostatic wall will begin approximately 47' east of the common property line shared by 6809 and 6813 Pasa Tiempo Circle, respectively. From this point of origin, the proposed wall will be installed at the defined rear property line and extend westerly for approximately 151 LF, ending at 6817 Pasa Tiempo Circle. The proposed footing of the structural wall will be connected via dowels to the existing channel embankment wall. All grades will be finished to promote positive drainage throughout.

Outlet at Mulberry Dam: Demolition and removal of existing channel features damaged by "Storm 2006" include existing concrete channel embankment slopes, mortared rock riprap apron, and downstream accumulated debris. The existing west face of the channel desilting basin will be saw cut in a series of trenches to drain said basin. Channel improvements consist of 85 strategically placed energy dissipators, a 3 foot concrete drop structure, and 50 LF of 18" (minimum) loose non-mortared rock riprap in lieu of a concrete apron. The 6' deep concrete lined channel will be 12" thick with # 4 rebar each way, top and bottom with 3" cover. The new channel will have channel embankment slopes set at 2 (H) to 1 (V) side slopes and retain natural escarpment slopes with structural retaining walls ranging in size from 4' to 6' (maximum). Proposed channel configuration will provide for a 15' access ramp ascending from the downstream location of the channel up at a 6% rise to the top of the proposed drop structure. A proposed south concrete retaining wall will extend approximately 231 LF beyond the end of the concrete lined channel to help in routing storm

runoff to its proper destination within the Mulberry Dam. The said south retaining wall will be mounted with a 2" diameter galvanized handrail for the duration of its length.

All construction installation and practices shall meet and/or exceed City of El Paso Engineering Standards and all other applicable state and federal codes and regulations.

NOTES:

The project will be accomplished as shown below or as approved by the City of El Paso Engineering Department. All work shall begin at Notice to Proceed, and must be completed within the indicated time frame.

- No Construction Phasing is planned for any or all of the planned improvements stated herein. A Notice-to-Proceed (NTP) shall be issued for this project and liquidated damages shall apply at the end of the project duration.

The description of this scope of work, as shown above, is only a general overview of this project. Contractor shall refer to the project plans, specifications and Engineering Department official for further information.

The undersigned Bidder agrees to commence work on a date to be specified in a written Notice to Proceed and to substantially complete the work on which he/she has bid within **Ninety (90) Consecutive Calendar Days**. Bidder agrees to pay as liquidated damages the sum of **\$350.00 DOLLARS** for each consecutive calendar day thereafter as provided in paragraph 6.8 of the General Conditions of the Contract.

THIS IS A UNIT PRICE PROJECT

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: HIGH RIDGE AND BEAR RIDGE CHANNEL DRAINAGE IMPROVEMENTS
 BID DATE: JUNE 27, 2007

BID NO.: 2007-209
 Dept: Street

				C. F. JORDAN, L.P. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS		J. A. R. CONCRETE, INC. EL PASO, TEXAS					
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID		UNIT PRICE SCHEDULE											
1	1	L.S.	CLEAR & GRUB	\$30,000.00	\$30,000.00	\$30,000.00	\$30,000.00	\$102,000.00	\$102,000.00		\$0.00		\$0.00
2	180	S.Y.	REMOVE & DISPOSE CONCRETE AS PER PLANS	\$40.00	\$7,200.00	\$33.00	\$5,940.00	\$43.00	\$7,740.00		\$0.00		\$0.00
3	70	L.F.	REMOVE & DISPOSE OF ROCKWALL AS PER PLANS	\$45.00	\$3,150.00	\$40.00	\$2,800.00	\$38.00	\$2,660.00		\$0.00		\$0.00
4	4	EACH	CONCRETE CUT AS PER PLANS	\$6,000.00	\$24,000.00	\$650.00	\$2,600.00	\$2,400.00	\$9,600.00		\$0.00		\$0.00
5	616	C.Y.	COMPACTED BACKFILL (FILL)	\$60.00	\$36,960.00	\$38.00	\$23,408.00	\$37.00	\$22,792.00		\$0.00		\$0.00
6	1	L.S.	CHANNEL EMBANK- MENT WALL DOWEL- ING AS SHOWN ON PLANS	\$18,000.00	\$18,000.00	\$4,000.00	\$4,000.00	\$2,700.00	\$2,700.00		\$0.00		\$0.00
7	151	L.F.	REINFORCED STRUCTURAL (HYDROSTATIC) WALL AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$595.00	\$89,845.00	\$400.00	\$60,400.00	\$380.00	\$57,380.00		\$0.00		\$0.00
8	11,175	C.Y.	EXCAVATION (CUT WASTE)	\$12.00	\$134,100.00	\$9.00	\$100,575.00	\$13.00	\$145,275.00		\$0.00		\$0.00
9	3,756	S.Y.	SUBGRADE SOIL PREPARATION (SLOPES AND CHANNEL BOTTOM)	\$5.00	\$18,780.00	\$4.00	\$15,024.00	\$5.00	\$18,780.00		\$0.00		\$0.00
10	173	S.Y.	FURNISH & INSTALL 4" REINFORCED CONCRETE RIPRAP (COMPLETE IN PLACE)	\$90.00	\$15,570.00	\$90.00	\$15,570.00	\$144.00	\$24,912.00		\$0.00		\$0.00

APPROVED BY: *Mwp 6-28-07*

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: HIGH RIDGE AND BEAR RIDGE CHANNEL DRAINAGE IMPROVEMENTS
 BID DATE: JUNE 27, 2007

BID NO.: 2007- 209
 Dept: Street

				C. F. JORDAN, L.P. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS		J. A. R. CONCRETE, INC. EL PASO, TEXAS					
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID UNIT PRICE SCHEDULE													
11	35	S.Y.	FURNISH & INSTALL 6" REINFORCED CONCRETE RIPRAP (COMPLETE IN PLACE)	\$145.00	\$5,075.00	\$140.00	\$4,900.00	\$120.00	\$4,200.00		\$0.00		\$0.00
12	71	S.Y.	FURNISH & INSTALL 6" REINFORCED CONCRETE FOR SIDEWALK, DRIVEWAY, SLABS (COMPLETE IN PLACE)	\$85.00	\$6,035.00	\$75.00	\$5,325.00	\$53.00	\$3,763.00		\$0.00		\$0.00
13	30	L.F.	FURNISH & INSTALL 6" (STANDARD VERTICAL) CURB & GUTTER	\$35.00	\$1,050.00	\$15.00	\$450.00	\$16.00	\$480.00		\$0.00		\$0.00
14	30	L.F.	FURNISH & INSTALL 6" CHAIN LINK FENCE W/3 STRAND BARBED WIRE COMPLETE IN PLACE	\$55.00	\$1,650.00	\$25.00	\$750.00	\$29.00	\$870.00		\$0.00		\$0.00
15	7	PERCH	FURNISH & INSTALL 3' HIGH ROCK WALL AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$270.00	\$1,890.00	\$160.00	\$1,120.00	\$155.00	\$1,085.00		\$0.00		\$0.00
6	832	C.Y.	COMPACTED SELECT BACKFILL (CUTFILL)	\$60.00	\$49,920.00	\$34.00	\$28,288.00	\$26.00	\$21,632.00		\$0.00		\$0.00
17	848	C.Y.	FURNISH & INSTALL 12" REINFORCED CONCRETE (CHANNEL BOTTOM) AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$560.00	\$474,880.00	\$290.00	\$245,920.00	\$251.00	\$212,848.00		\$0.00		\$0.00

APPROVED BY: Mwp 6-28-07

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: HIGH RIDGE AND BEAR RIDGE CHANNEL DRAINAGE IMPROVEMENTS
 BID DATE: JUNE 27, 2007

BID NO.: 2007- 209
 Dept: Street

		C. F. JORDAN, L.P. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS		J. A. R. CONCRETE. INC. EL PASO, TEXAS							
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID		UNIT PRICE SCHEDULE											
18	233	C.Y.	FURNISH & INSTALL 12" REINFORCED CONCRETE (CHANNEL SLOPES) AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$560.00	\$130,480.00	\$320.00	\$74,560.00	\$270.00	\$62,910.00		\$0.00		\$0.00
19	85	EACH	FURNISH & INSTALL REINFORCED CONCRETE ENERGY DISSIPATORS AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$600.00	\$51,000.00	\$450.00	\$38,250.00	\$474.00	\$40,290.00		\$0.00		\$0.00
20	174	L.F.	FURNISH & INSTALL RETAINING WALL STRUCTURE (H=4') AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$350.00	\$60,900.00	\$315.00	\$54,810.00	\$103.00	\$17,922.00		\$0.00		\$0.00
21	300	L.F.	FURNISH & INSTALL RETAINING WALL STRUCTURE (H=6") AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$380.00	\$114,000.00	\$230.00	\$69,000.00	\$170.00	\$51,000.00		\$0.00		\$0.00
22	340	L.F.	FURNISH & INSTALL 2" DIAMETER HANDRAIL (GALV. SCH 20) AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$75.00	\$25,500.00	\$40.00	\$13,600.00	\$23.00	\$7,820.00		\$0.00		\$0.00
23	400	C.Y.	FURNISH & INSTALL LOOSE ROCK RIPRAP (4-18") AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$72.00	\$28,800.00	\$120.00	\$48,000.00	\$130.00	\$52,000.00		\$0.00		\$0.00

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: HIGH RIDGE AND BEAR RIDGE CHANNEL DRAINAGE IMPROVEMENTS
 BID DATE: JUNE 27, 2007

BID NO.: 2007- 209
 Dept: Street

				C. F. JORDAN, L.P. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS		J. A. R. CONCRETE. INC. EL PASO, TEXAS					
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)	UNIT BID PRICE (In figures)	Total Amount (Quantity x Unit Price)(In Figures)
BASE BID UNIT PRICE SCHEDULE													
24	200	S.Y.	FURNISH & INSTALL MORTARED ROCK RIPRAP (d=8") AS SHOWN ON PLANS (COMPLETE IN PLACE)	\$75.00	\$15,000.00	\$70.00	\$14,000.00	\$62.00	\$12,400.00		\$0.00		\$0.00
25	1	L.S.	STORM WATER POLLUTION PREVENTION PLAN (COMPLETE IN PLACE)	\$24,000.00	\$24,000.00	\$20,000.00	\$20,000.00	\$50,000.00	\$50,000.00		\$0.00		\$0.00
SUM TOTAL BASE BID (ITEM NOS. 1 - 25)					\$1,367,785.00		\$879,290.00		\$933,059.00		\$0.00		\$0.00
BID BOND SUBMITTED					YES		YES		YES				
AMENDMENTS ACKNOWLEDGED					None Issued		None Issued		None Issued				

APPROVED BY: *MWP 6-28-07*

CONTRACT

IN WITNESS, WHEREOF, the parties to these presents have executed this Contract on the 6th day of JULY, 2007 in two (2) counterparts, each of which shall be deemed an original, in the year and day first above mentioned.

OWNER – CITY OF EL PASO

by Joyce A. Wilson
City Manager Joyce Wilson

APPROVED AS TO FORM:

Bob A. Orr
Assistant City Attorney

Contractor: Dan Williams Co.
by D.C. Williams
D.C. Williams - President

PROCESSED BY FINANCIAL SERVICES:

[Signature]
Financial Services

Typed Name & Title
4730 RIPLEY EL PASO, TX 79927
Address, City, State, Zip Code

915-584-8691 915-833-5289
Telephone Number Fax Number

PROCESSED BY ENGINEERING:

[Signature]
for City Engineer

If the Contractor be a corporation, the following certificate should be executed:

I, DANIELA ROTH, certify that I am the ASSISTANT Secretary of the corporation named as Bidder, hereinabove; and that D.C. Williams, who signed the foregoing Contract on behalf of the Bidder was then PRESIDENT of said corporation; that said proposal was duly signed for and in behalf of said corporation by authority of its governing body, and is within the scope of its corporate powers.

[Signature]
CORPORATE SECRETARY SIGNATURE AND CORPORATE SEAL