

**CITY OF EL PASO, TEXAS
AGENDA ITEM
DEPARTMENT HEAD'S SUMMARY FORM**

DEPARTMENT: Transportation

AGENDA DATE: September 14, 2010

CONTACT PERSON NAME AND PHONE NUMBER: R. Alan Shubert, P.E., City Engineer X4423 & Daryl W. Cole, Department of Transportation Director, 621-6750

DISTRICT(S) AFFECTED: ALL

SUBJECT:

Discussion and action on award of Solicitation No. 2010-256 for Citywide Repair or Construction of Parkway Structures 2010-2012 to J.A.R. Construction, Inc., for a total amount of \$3,892,657.50. This is a low bid, unit-priced contract. J.A.R. Construction, Inc. is the lowest responsible, responsive bidder.

BACKGROUND / DISCUSSION:

We have reviewed the above subject bid and we recommend that the contract be awarded to J.A.R. Construction, Inc., as the lowest bidder, most responsive and responsible bidder meeting specifications, for an estimated amount of \$3,892,657.50.

Base Bid I:	\$2,256,277.50
Base Bid II:	<u>\$1,636,380.00</u>

Sum Total Base Bid I and II : **\$3,892,657.50**

This is a two year requirements contract, with options to extend 365 days or 730 days. Work under the unit price component is only an estimated value and will be ordered, performed, invoiced and paid by measured quantity. The actual cost of the unit price component will be the sum of total of unit prices at the end of the contract term.

PRIOR COUNCIL ACTION:

N/A

AMOUNT AND SOURCE OF FUNDING:


\$3,892,657.50 2006 Certificates of Obligation, Department of Transportation General Fund, Community Development Block Grant and Sun Metro

BOARD / COMMISSION ACTION:

Item on Mass Transit Board Agenda 9/14/2010.

*****REQUIRED AUTHORIZATION*****

DEPARTMENT HEAD:


(If Department Head Summary Form is initiated by Purchasing, client department should sign also)

Information copy to appropriate Deputy City Manager



RECOMMENDATION

DATE: August 9, 2010
TO: R. Alan Shubert, P.E., City Engineer
ATTN: Rachel Johnson, Project Compliance Specialist
COPY TO: Michelle LePage, Contracts Development Coordinator
FROM: Daryl W. Cole, Streets Director *DW Cole 8/9/10*
SUBJECT: 2010-256 Citywide Repair or Construction of Parkway Structures 2010-2012

We have reviewed the above referenced subject bid and we recommend that the contract be awarded to **J.A.R. Construction, Inc.**, as the lowest, most responsive bidder meeting specifications. Base Bid I \$2,256,277.50 and base bid II \$1,636,380.00. Total estimated contract award of \$3,892,657.50.

This is a two years requirement contract, with options to extend 365 days or 730 days. Work under the unit price component is only an estimated value and will be ordered, performed, invoiced and paid by measured quantity. The actual cost of the unit price component will be the sum of total of unit prices at the end of the contract term.

If you have any questions, I may be reached at 621-6750.

Mayor
John F. Cook

City Council

District 1
Ann Morgan Lilly

District 2
Susie Byrd

District 3
Emma Acosta

District 4
Carl L. Robinson

District 5
Rachel Quintana

District 6
Eddie Holgun Jr.

District 7
Steve Ortega

District 8
Beto O'Rourke

City Manager
Joyce A. Wilson



Street Department - Daryl W. Cole, Director

**Citywide Repair or Construction of
Parkway Structures 2010-2012
Solicitation No. 2010-256**

Scope of Work

Base Bid I

Provide all labor, materials, equipment, and traffic control for the demolition, removal, disposal, construction, and installation of various concrete structures. These concrete structures include sidewalks, curb and gutter, driveways, drainage flumes, wheelchair ramps, median cuts, foundations, footings, slabs, bus pads, channel lining, paving, jersey barriers, drop inlets, stamped colored concrete, concrete rip rap, and penetration aprons.

Provide all labor, materials, equipment, and traffic control for demolition, removal, disposal, construction, and installation of various fencing structures. These fencing structures include garden rock-walls, retaining rock-walls, rock columns, rock riprap, wrought iron fencing, wrought iron gates, chain-link fencing, and chain-link gates.

This work will include clearing, grubbing, excavation, demolition, subgrade preparation, site preparation, earthwork, backfilling, compaction and off-site proper disposal of generated debris, including subsoil. Also including, but not limited to the removal, replacement, relocation, trimming and adjustment as needed of miscellaneous improvements such as mailboxes, traffic signs, utility boxes, trees, bushes, shrubs and irrigation lines/systems throughout the City of El Paso.

Base Bid II

Provide all labor, materials, equipment, traffic control, and tools necessary for the installation of underground conduit, ground boxes, concrete foundations, and loop detectors at various locations citywide.

This work will include clearing, grubbing, excavation, demolition, subgrade preparation, site preparation, earthwork, backfilling, compaction and off-site proper disposal of generated debris, including subsoil. Also including, but not limited to, the removal, replacement, relocation, trimming and adjustment as needed of miscellaneous improvements such as mailboxes, traffic signs, utility boxes, trees, bushes, shrubs and irrigation lines/systems throughout the City of El Paso.

General Requirements

Contractor shall follow all contract requirements with emphasis on the following points.

- Traffic control will be in accordance with the latest Manual of Uniform Traffic Control Devices (MUTCD).
- All construction work pertaining to pedestrian paths of travel, must meet the following current standards as applicable to each project.
 - Texas Department of Licensing and Regulation (TDLR)
 - Texas Accessibility Standards (TAS) requirements
 - Americans with Disabilities Act (ADA) requirements
- All construction work must meet the following current standards where applicable
 - City of El Paso Design Standards for Construction (DSC)
 - Texas Department of Transportation (TxDOT) Construction Standards
- Stamping of Contractor's logo is prohibited.
- The contractor **shall respond** to a request for a cost proposal within two (2) working days of such request. A separate Notice to Proceed will be issued for each job locality and shall indicate a completion date for that work. Liquidated damages apply to each job locality and associated Notice to Proceed.
- Contractor shall provide Performance and Payment bonds for 100% value of the total estimated amount of award contract amount. Distribute the cost of these bonds throughout the line items.
- The contractor shall keep on the project at all times during its progress a qualified, competent, Resident Superintendent. The Resident Superintendent shall be fluent in English and capable of communicating with the public, Engineer, Inspector and Owner.
- Provide temporary toilets, wash facilities, and drinking water facilities with potable water approved by local health authorities. Must supply and maintain toilet tissue, paper towels, paper cups and similar disposable materials as appropriate for each facility and provide appropriate covered waste containers for used materials.
- The Contractor shall be responsible for any damage to private property caused by the construction project.

The estimated quantities indicated in the proposal are only estimated quantities. The estimated quantities do not guarantee the quantity of work for the Contractor; rather, the actual quantity of work shall be dependent on the total of all purchase orders issued to the Contractor at the sole discretion of the City. The actual quantity of work may vary from the estimated quantities herein. Work to be performed is subject to funding availability and user department requests. No money has been appropriated for this project at the time of bidding.

THIS IS A UNIT PRICE CONTRACT

CITY OF EL PASO BID TABULATION

BID TITLE:	CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012	BID NO: 2010-256
BID DATE:	August 4, 2010	DEPARTMENT: STREETS

	J.A.R. CONSTRUCTION, INC. EL PASO, TX	MARTINEZ BROS. EL PASO, TX					
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL

BASE BID I - UNIT PRICE SCHEDULE

1	128,000	SF	4-INCH SIDEWALK (PLACEMENT) - REFER TO THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION (DSC) SECTION 6 FOR DETAILS FOR THE SUM OF:	\$1.25	\$160,000.00	\$1.19	\$152,320.00
2	121,000	SF	4-INCH SIDEWALK (REPLACEMENT) - REFER TO THE SDC SECTION 6 FOR DETAILS FOR THE SUM OF:	\$5.00	\$605,000.00	\$4.98	\$602,580.00
3	1,500	SF	4-INCH SIDEWALK REINFORCED/6-INCH NON-REINFORCED (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS FOR THE SUM OF:	\$5.00	\$7,500.00	\$5.30	\$7,950.00
4	1,500	SF	4-INCH SIDEWALK REINFORCED/6-INCH NON-REINFORCED (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS FOR THE SUM OF:	\$6.00	\$9,000.00	\$6.20	\$9,300.00
5	9,400	SF	6-INCH CONCRETE STEM-WALLS (PLACEMENT) - REFER TO DETAIL NO. 3 FOR THE SUM OF:	\$7.00	\$65,800.00	\$8.60	\$80,840.00
6	330	LF	6-INCH CONCRETE STEM-WALL (REPLACEMENT) - REFER TO DETAIL NO. 3 FOR THE SUM OF:	\$8.00	\$2,640.00	\$9.45	\$3,118.50
7	1,200	LF	CURB AND GUTTER (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$6.00	\$7,200.00	\$8.90	\$10,680.00
8	12,000	LF	CURB AND GUTTER (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$20.00	\$240,000.00	\$19.98	\$239,760.00
9	1,400	LF	HEADER CURB FOR EXPANSIVE SOIL (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$6.00	\$8,400.00	\$6.40	\$8,960.00

Approved By:

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012
 BID DATE: August 4, 2010
 BID NO: 2010-256
 DEPARTMENT: STREETS

			J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX		
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	
10	50	LF	HEADER CURB FOR EXPANSIVE SOIL (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$5.00	\$250.00	\$9.00	\$450.00	
11	670	LF	STANDARD CURB (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$5.00	\$3,350.00	\$6.00	\$4,020.00	
12	1,400	LF	STANDARD CURB (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$21.00	\$29,400.00	\$19.00	\$26,600.00	
13	130	LF	TxDOT PINNED CURB (PLACEMENT) - REFER TO TxDOT FOR APPLICABLE DETAILS FOR THE SUM OF:	\$9.00	\$1,170.00	\$11.00	\$1,430.00	
14	110	LF	TxDOT PINNED CURB (REPLACEMENT) - REFER TO TxDOT FOR APPLICABLE DETAILS FOR THE SUM OF:	\$14.00	\$1,540.00	\$15.00	\$1,650.00	
15	250	LF	6-INCH ROLLED CURB (PLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$6.00	\$1,500.00	\$7.60	\$1,900.00	
16	50	LF	6-INCH ROLLED CURB (REPLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$8.00	\$400.00	\$10.00	\$500.00	
17	3,300	SF	4-INCH REINFORCED/6-INCH NON-REINFORCED CONCRETE RESIDENTIAL DRIVEWAY (PLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$4.00	\$13,200.00	\$3.50	\$11,550.00	
18	5,200	SF	4-INCH REINFORCED/6-INCH NON-REINFORCED CONCRETE RESIDENTIAL DRIVEWAY (REPLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS FOR THE SUM OF:	\$4.50	\$23,400.00	\$5.00	\$26,000.00	

Approved By: *ML*

CITY OF EL PASO BID TABULATION

BID TITLE:		CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012					BID NO: 2010-256	
BID DATE:		August 4, 2010					DEPARTMENT: STREETS	
		J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	
19	2,400	SF	6-INCH CONCRETE COMMERCIAL DRIVEWAY (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS FOR THE SUM OF:	\$3.50	\$8,400.00	\$4.00	\$9,600.00	
20	9,000	SF	6-INCH CONCRETE COMMERCIAL DRIVEWAY (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS FOR THE SUM OF:	\$6.00	\$54,000.00	\$6.15	\$55,350.00	
21	9,200	SF	WHEELCHAIR RAMP / CURB CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) (PLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS FOR THE SUM OF:	\$6.50	\$59,800.00	\$9.75	\$89,700.00	
22	53,000	SF	WHEELCHAIR RAMP / CURB CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) RE(PLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS FOR THE SUM OF:	\$10.00	\$530,000.00	\$10.90	\$577,700.00	
23	30	SF	WHEELCHAIR RAMP / CURB CUT WITH CONCRETE PAVERS (PLACEMENT) REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS FOR THE SUM OF:	\$10.00	\$300.00	\$14.00	\$420.00	
24	50	SF	WHEELCHAIR RAMP / CURB CUT WITH CONCRETE PAVERS (REPLACEMENT) REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS FOR THE SUM OF:	\$13.00	\$650.00	\$17.00	\$850.00	
25	300	SF	MEDIAN RAMP/CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) (PLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS FOR THE SUM OF:	\$7.00	\$2,100.00	\$12.00	\$3,600.00	
26	800	SF	MEDIAN RAMP/CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) (REPLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS FOR THE SUM OF:	\$11.00	\$8,800.00	\$14.00	\$11,200.00	
27	3,000	SF	DRAINAGE FLUME (PLACEMENT) - REFER TO DSC SECTION 2 FOR DETAILS FOR THE SUM OF:	\$8.00	\$24,000.00	\$9.00	\$27,000.00	

Approved By: *ML*

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012
 BID DATE: August 4, 2010
 BID NO: 2010-256
 DEPARTMENT: STREETS

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
28	600	PERCH	DRAINAGE FLUME (REPLACEMENT) - REFER TO DSC SECTION 2 FOR DETAILS FOR THE SUM OF:	\$9.00	\$5,400.00	\$11.00	\$6,600.00		
29	10	PERCH	ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$65.00	\$650.00	\$145.00	\$1,450.00		
30	80	PERCH	ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$67.00	\$5,360.00	\$170.00	\$13,600.00		
31	60	PERCH	RETAING ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$91.00	\$5,460.00	\$145.00	\$8,700.00		
32	10	PERCH	RETAING ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$71.00	\$710.00	\$175.00	\$1,750.00		
33	40	PERCH	RED ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$170.00	\$6,800.00	\$200.00	\$8,000.00		
34	10	PERCH	RED ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$170.00	\$1,700.00	\$225.00	\$2,250.00		
35	2,200	SF	ROCKWALL RE-POINTING I INCLUDES PREPARATION AND CLEANING OF XISTING JOINTS AND RE-POINTING WITH COLOR MATCHED PORTLAND CEMENT MORTAR (2,500 PSI) REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$3.00	\$6,600.00	\$5.30	\$11,660.00		
36	170	PERCH	ROCK RIP RAP (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$95.00	\$16,150.00	\$130.00	\$22,100.00		

Approved By: *MLK*

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012
 BID DATE: August 4, 2010
 BID NO: 2010-256
 DEPARTMENT: STREETS

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
37	14	PERCH	ROCK RIP RAP (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$70.00	\$980.00	\$150.00	\$2,100.00		
38	10	PERCH	ROCKWALL COLUMNS (PLACEMENT) - REFER TO DETAIL 13 FOR THE SUM OF:	\$202.00	\$2,020.00	\$330.00	\$3,300.00		
39	10	PERCH	ROCKWALL COLUMNS (REPLACEMENT) - REFER TO DETAIL 13 FOR THE SUM OF:	\$202.00	\$2,020.00	\$365.00	\$3,650.00		
40	100	SY	4 - INCH REINFORCED CONCRETE SLAB (PLACEMENT) - REFER TO DETAIL 14 FOR THE SUM OF:	\$14.00	\$1,400.00	\$26.00	\$2,600.00		
41	150	SY	6 - INCH REINFORCED CONCRETE SLAB (PLACEMENT) - REFER TO DETAIL 14 FOR THE SUM OF:	\$18.00	\$2,700.00	\$32.00	\$4,800.00		
42	130	SY	REINFORCED FOOTING FOR CONCRETE SLAB OR ROCKWALLS (PLACEMENT) - REFER TO DETAIL 14 FOR THE SUM OF:	\$30.00	\$3,900.00	\$50.00	\$6,500.00		
43	2	EACH	CONCRETE BUS PAD W/ APPROACH CONCRETE PAD (PLACEMENT) - REFER TO THE DSC SECTION 3 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$7,000.00	\$14,000.00	\$7,500.00	\$15,000.00		
44	100	SY	8 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17 FOR THE SUM OF:	\$71.00	\$7,100.00	\$76.00	\$7,600.00		
45	100	SY	8 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17 FOR THE SUM OF:	\$98.00	\$9,800.00	\$100.00	\$10,000.00		

Approved By: *ML*

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012
 BID DATE: August 4, 2010
 BID NO: 2010-256
 DEPARTMENT: STREETS

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
46	100	SY	10 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17 FOR THE SUM OF:	\$77.00	\$7,700.00	\$95.00	\$9,500.00		
47	500	SY	10 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17 FOR THE SUM OF:	\$90.00	\$45,000.00	\$110.00	\$55,000.00		
48	100	SY	12 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17 FOR THE SUM OF:	\$85.00	\$8,500.00	\$113.00	\$11,300.00		
49	400	SY	12 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17 FOR THE SUM OF:	\$106.00	\$42,400.00	\$116.00	\$46,400.00		
50	5	CY	JERSEY BARRIER, DECORATIVE, FLUTED, REINFORCED CONCRETE STRUCTURE (PLACEMENT) - INCLUDES REQUIRED FORMING, REINFORCED CONCRETE PLACEMENT AND REBAR FOR THE SUM OF:	\$500.00	\$2,500.00	\$600.00	\$3,000.00		
51	5	CY	JERSEY BARRIER, DECORATIVE, FLUTED, REINFORCED CONCRETE STRUCTURE (REPLACEMENT) - INCLUDES REQUIRED FORMING, REINFORCED CONCRETE PLACEMENT AND REBAR FOR THE SUM OF:	\$700.00	\$3,500.00	\$800.00	\$4,000.00		
52	20	CY	MISCELLANEOUS REINFORCED CONCRETE STRUCTURE (DRAINAGE INLETS AND OUTLETS, MANHOLES) REPAIR (PLACEMENT) - REFERENCE THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION SECTION 2 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$420.00	\$8,400.00	\$410.00	\$8,200.00		
53	12	CY	MISCELLANEOUS REINFORCED CONCRETE STRUCTURE (DRAINAGE INLETS AND OUTLETS, MANHOLES) REPAIR (REPLACEMENT) - REFERENCE THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION SECTION 2 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$600.00	\$7,200.00	\$500.00	\$6,000.00		
54	350	SY	CONCRETE CHANNEL LINING (PLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$10.00	\$3,500.00	\$40.00	\$14,000.00		

Approved By: 

CITY OF EL PASO BID TABULATION

BID TITLE:		CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012					BID NO: 2010-256	
BID DATE:		August 4, 2010					DEPARTMENT: STREETS	
		J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	
55	130	SY	CONCRETE CHANNEL LINING (REPLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$12.00	\$1,560.00	\$49.00	\$6,370.00	
56	10	CY	8 - INCH REINFORCED RETAINING CONCRETE WALL (PLACEMENT) - TO INCLUDE REQUIRED FORMING, REBAR, AND FOOTING. FOOTING NOT PAID AS A SEPARATE LINE ITEM. SEE DETAIL 21 FOR THE SUM OF:	\$175.00	\$1,750.00	\$260.00	\$2,600.00	
57	10	CY	8 - INCH REINFORCED RETAINING CONCRETE WALL (REPLACEMENT) - TO INCLUDE REQUIRED FORMING, REBAR, AND FOOTING. FOOTING NOT PAID AS A SEPARATE LINE ITEM. SEE DETAIL 21 FOR THE SUM OF:	\$150.00	\$1,500.00	\$420.00	\$4,200.00	
58	10	SY	ADD EXPOSED AGGREGATE TEXTURE FINISH USING 3/4 - INCH MAX RIVER ROCK, FOR THE SUM OF:	\$4.75	\$47.50	\$5.30	\$53.00	
59	40	SY	ADD CONCRETE INTEGRATED COLOR TINT, FOR THE SUM OF:	\$9.00	\$360.00	\$10.00	\$400.00	
60	170	SF	WROUGHT IRON GATE, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM:	\$8.00	\$1,360.00	\$10.00	\$1,700.00	
61	20	SF	WROUGHT IRON GATE, VARIABLE HEIGHT, (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM:	\$10.00	\$200.00	\$11.00	\$220.00	
62	20	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$8.00	\$160.00	\$9.00	\$180.00	
63	10	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$11.00	\$110.00	\$12.00	\$120.00	

Approved By: *ML*

CITY OF EL PASO BID TABULATION

BID TITLE:	CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012	BID NO: 2010-256
BID DATE:	August 4, 2010	DEPARTMENT: STREETS

			J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX		
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	
64	1,200	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT WITH 1 FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$7.00	\$8,400.00	\$6.00	\$7,200.00	
65	100	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT WITH 1 FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$12.00	\$1,200.00	\$10.00	\$1,000.00	
66	1,500	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT, (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF: FOR THE SUM OF:	\$7.00	\$10,500.00	\$6.00	\$9,000.00	
67	800	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT, (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF: FOR THE SUM OF:	\$9.00	\$7,200.00	\$7.00	\$5,600.00	
68	170	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT WITH 1-FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC	\$9.00	\$1,530.00	\$11.00	\$1,870.00	
69	160	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT WITH 1-FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC	\$10.00	\$1,600.00	\$12.00	\$1,920.00	
70	160	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT, (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$9.00	\$1,440.00	\$11.00	\$1,760.00	
71	190	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT, (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$10.00	\$1,900.00	\$12.00	\$2,280.00	
72	10	EACH	PARKING METER PIPE (PLACEMENT) - INCLUDES FABRICATION AND INSTALLATION OF PIPE, SAW-CUTS, CORING, CONCRETE PLACEMENT AND MATCHING TO EXISTING SURFACE FINISH. SEE DETAIL 25 FOR THE SUM OF:	\$120.00	\$1,200.00	\$100.00	\$1,000.00	

Approved By: *mk*

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012
 BID DATE: August 4, 2010
 BID NO: 2010-256
 DEPARTMENT: STREETS

		J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX				
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
73	10	SF	PARKING METER PIPE (REPLACEMENT) - INCLUDES FABRICATION AND INSTALLATION OF PIPE, SAW-CUTS, CORING, CONCRETE PLACEMENT AND MATCHING TO EXISTING SURFACE FINISH. SEE DETAIL 25 FOR THE SUM OF:	\$150.00	\$1,500.00	\$200.00	\$2,000.00		
74	10	SF	PARKING METERS PIPE BASE PLATE MOUNT (PLACEMENT) - INCLUDES BOLT PLATE AND INSTALLATION. SEE DETAIL 25 FOR THE SUM OF:	\$120.00	\$1,200.00	\$80.00	\$800.00		
75	10	EACH	PARKING METERS PIPE BASE PLATE MOUNT (REPLACEMENT) - INCLUDES BOLT PLATE AND INSTALLATION. SEE DETAIL 25 FOR THE SUM OF:	\$120.00	\$1,200.00	\$100.00	\$1,000.00		
76	1,000	SY	4-INCH STAMPED COLORED CONCRETE (PLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SEE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326. FOR THE SUM OF:	\$39.00	\$39,000.00	\$27.50	\$27,500.00		
77	1,200	SY	4-INCH STAMPED COLORED CONCRETE (REPLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SEE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326. FOR THE SUM OF:	\$28.00	\$33,600.00	\$31.50	\$37,800.00		
78	20	SY	6-INCH REINFORCED STAMPED COLORED CONCRETE (PLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326, FOR THE SUM OF:	\$42.00	\$980.00	\$42.00	\$840.00		
79	10	SY	6-INCH REINFORCED STAMPED COLORED CONCRETE (REPLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326, FOR THE SUM OF:	\$178.00	\$1,780.00	\$55.00	\$550.00		

Approved By: *ML*

CITY OF EL PASO BID TABULATION

BID TITLE:		CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012						BID NO: 2010-256	
BID DATE:		August 4, 2010						DEPARTMENT: STREETS	
				J.A.R. CONSTRUCTION, INC. EL PASO, TX		MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
80	2	EACH	CITY MONUMENTS (PLACEMENT) - INSTALLATION WILL INCLUDE CONCRETE BASE, CITY MONUMENT, MONUMENT HOUSING AND LID. A LICENSED SURVEYOR MUST SET THE MONUMENT AND PROVIDE ELEVATION CERTIFICATION. REFER TO THE DSC SECTION 3 FOR DETAILS FOR THE SUM OF:	\$550.00	\$1,100.00	\$800.00	\$1,600.00		
81	10	SY	CONCRETE PAVERS (REPLACEMENT) - SEE THE DETAIL 28 AT THE END OF THIS SECTION FOR THE SUM OF:	\$65.00	\$650.00	\$55.00	\$550.00		
82	10	EACH	6-INCH REINFORCED CONCRETE APRON, (PLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$190.00	\$1,900.00	\$300.00	\$3,000.00		
83	70	EACH	ADJUSTMENT OF MANHOLES - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS FOR THE SUM OF:	\$190.00	\$13,300.00	\$280.00	\$19,600.00		
84	320	CY	TWO-SACK BACKFILL FOR THE SUM OF:	\$90.00	\$28,800.00	\$90.00	\$28,800.00		
SUM TOTAL - BASE BID I (ITEMS 1-84)					\$2,256,277.50		\$2,425,601.50		

Approved By: *mk*

CITY OF EL PASO BID TABULATION

BID TITLE:		CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012					BID NO: 2010-256	
BID DATE:		August 4, 2010					DEPARTMENT: STREETS	
		J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE.	TOTAL	UNIT PRICE	TOTAL	
1	5,000	LF	PVC CONDUIT 3-INCH INSTALLED BY TRENCHING TO INCLUDE, SAWCUT, EXCAVATION, BACKFILL COMPACTION, PAVEMENT REMOVAL & PATCHING, JAND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATION; FOR THE SUM OF:	\$13.20	\$66,000.00	\$14.80	\$74,000.00	
2	15,000	LF	PVC CONDUIT 2-INCH INSTALLED BY TRENCHING TO INCLUDE, SAWCUT, EXCAVATION, BACKFILL COMPACTION, PAVEMENT REMOVAL & PATCHING, JAND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATION; FOR THE SUM OF:	\$12.60	\$189,000.00	\$11.55	\$173,250.00	
3	5,000	LF	PVC CONDUIT 3-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$21.00	\$105,000.00	\$21.00	\$105,000.00	
4	20,000	LF	PVC CONDUIT 2-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$16.80	\$336,000.00	\$18.90	\$378,000.00	
5	175	EACH	GROUND BOX TYPE A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$540.00	\$94,500.00	\$1,030.00	\$180,250.00	
6	40	EACH	GROUND BOX TYPE C INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$720.00	\$28,800.00	\$1,275.00	\$51,000.00	
7	175	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 24A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$540.00	\$94,500.00	\$300.00	\$52,500.00	
8	80	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 30A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$660.00	\$52,800.00	\$340.00	\$27,200.00	
9	40	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 36A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$780.00	\$31,200.00	\$404.00	\$16,160.00	

Approved By: *mh*

CITY OF EL PASO BID TABULATION

BID TITLE:	CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012	BID NO: 2010-256
BID DATE:	August 4, 2010	DEPARTMENT: STREETS

			J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX		
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	
10	20	EACH	FOUNDATION, TRAFFIC CONTROLLER INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS, FOR THE SUM OF:	\$2,100.00	\$42,000.00	\$3,885.00	\$77,700.00	
11	175	EACH	GROUND BOX TYPE A REPLACEMENT: TO INCLUDE, NEW TYPE A GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$600.00	\$105,000.00	\$1,575.00	\$275,625.00	
12	40	EACH	GROUND BOX TYPE C REPLACEMENT: TO INCLUDE, NEW TYPE C GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$690.00	\$27,600.00	\$1,680.00	\$67,200.00	
13	72	EACH	GROUND BOX TYPE 1 REPLACEMENT: TO INCLUDE, NEW TYPE 1 GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$3,840.00	\$276,480.00	\$2,625.00	\$189,000.00	
14	5,000	LF	PVC CONDUIT 4-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$23.70	\$118,500.00	\$36.78	\$183,900.00	
15	5,000	LF	PVC CONDUIT 4-INCH INSTALLED BY TRENCHING: TO INCLUDE, SAW CUT, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$13.80	\$69,000.00	\$19.00	\$95,000.00	
SUM TOTAL - BASE BID II (ITEMS 1-15)				\$1,636,380.00		\$1,945,785.00		

Approved By: *ml*

CITY OF EL PASO BID TABULATION

BID TITLE:		CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2010-2012					BID NO: 2010-256	
BID DATE:		August 4, 2010					DEPARTMENT: STREETS	
		J.A.R. CONSTRUCTION, INC. EL PASO, TX			MARTINEZ BROS. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	
SUM TOTAL - BASE BID I AND BASE BID II				\$3,892,657.50		\$4,371,386.50		
A. OPTION 1 THREE HUNDRED SIXTY FIVE (365) DAY ADDITIONAL TERM.				YES		YES		
B. OPTION 2 SEVEN HUNDRED THIRTY (730) DAY ADDITIONAL TERM.				YES		NO		
BID BOND				YES		YES		

Approved By: *ML*