City of El Paso
Scope of Work

Storm 2006:Colonia Escondida Pump Station, Phase I
Solicitation No. 2008-018

BASE BID

The Colonia Escondida Pump Station Phase I consists of providing all labor, equipment, material and incidentals to reconstruct La Adelita and El Centauro Roads and the installation of approximately 705 feet of 30" Reinforced Concrete Pipe (RCP) and 1,225 feet of 24" PVC pipes.

The demolition and grading work consists of, but not limited to, removing and disposing of asphalt, base and subgrade and be replaced by a new structural section consisting of 2.5" of asphalt, 5" of base and 8" of cement treated subgrade.

Contractor shall include a traffic control plan for construction; approved by the City of El Paso's Traffic Division. Contractor shall submit traffic control plan no later than two weeks prior to commencement of construction.

Notes:

Contractor shall coordinate all construction activity with the City of El Paso Engineering Department Inspector. Also coordinate utility line spotting within street R.O.W., private property, or easements with appropriate utility companies.

The project will be accomplished as shown in the plan drawings/specifications or as approved by the City of El Paso Engineering Department. All work shall begin at Notice to Proceed, and must be completed within the time specified for this project in the notice to proceed.

- A Notice to Proceed shall be issued for the entire project and liquidated damages shall apply at the end of the project duration.

Prior to commencement of any work, contractor shall submit and obtain approval from El Paso Engineering Department for the Sequence of Construction, Schedule of Work, Traffic Control Plan (where applicable), and Haul/Waste Route to an approve disposal site.

The description of this scope of work, as shown, represents a general overview of this project. Contractor shall refer to the project plans, specifications and drawing details for further information.

This is a Unit Price Project.

THE STATE OF TEXAS }
COUNTY OF EL PASO }

CONTRACT

THIS AGREEMENT, made this 19th day of September, 2006 and between THE CITY OF EL PASO, County of El Paso, Texas, hereinafter called "Owner", acting herein through its City Manager, Joyce Wilson and Dan Williams Company (a corporation), of El Paso, COUNTY OF El Paso and STATE OF Texas, hereinafter called "Contractor".

WITNESSETH: That for and in consideration of the payments and agreements hereinafter mentioned, to be made and performed by the Owner, the Contractor hereby agrees with the Owner to commence and complete the construction described as follows:

Storm 2006:Colonia Escondida Pump Station, Phase I
Solicitation No. 2008-018

hereinafter called the "Project", for the sum of **Eight Hundred Thousand Eight Hundred** Dollars and **Zero** Cents **($800, 800.00)**, and all extra work in connection therewith, under the terms as stated in the contract documents; and at Contractor(s) own proper cost and expense to furnish all the materials, supplies, machinery, equipment, tools, superintendence, labor, insurance and other accessories and services necessary to complete the said Project, in accordance with the conditions and prices stated in the Proposal, the General Conditions, Supplemental General Conditions and Special Conditions of the Contract, the plans, which include all maps, plats, blueprints and other drawings and printed or written explanatory matter thereof, the specifications and contract documents thereof as furnished by the CITY ENGINEER or designated representative, and as enumerated in Paragraph 1.5 of the General Conditions, all of which are made a part hereof and collectively evidence and constitute the Contract.

The Contractor hereby agrees to commence work under this Contract on a date to be specified in a written "Notice to Proceed" from the Owner, and to substantially complete the project within **One Hundred Twenty (120)** consecutive calendar days thereafter. The Contractor further agrees to pay, as liquidated damages, the sum of **Five Hundred Dollars ($500.00)** for each consecutive calendar day thereafter, as hereinafter provided in Paragraph 6.8 of the General Conditions. The unit price quantities of this contract are estimated.

Base Bid	**$800,800.00**
Total Amount of Award:	**$800,800.00**

CONTRACT

IN WITNESS, WHEREOF, the parties to these presents have executed this Contract on the 19th day of OCTOBER, 2007 in two (2) counterparts, each of which shall be deemed an original, in the year and day first above mentioned.

OWNER – CITY OF EL PASO

by

City Manager Joyce Wilson

APPROVED AS TO FORM:

Assistant City Attorney

PROCESSED BY FINANCIAL SERVICES:

Financial Services

PROCESSED BY ENGINEERING:

City Engineer

Contractor: Dan Williams Company

by

D.C. Williams President

Typed Name & Title

4730 Ripley El Paso, Tx 79912

Address, City, State, Zip Code

915-833-5289 915-584-8691

Telephone Number Fax Number

If the Contractor be a corporation, the following certificate should be executed:

I, Barbara Roth, certify that I am the asst. Secretary of the corporation named as Bidder, hereinabove; and that D.C. Williams, who signed the foregoing Contract on behalf of the Bidder was then President of said corporation; that said proposal was duly signed for and in behalf of said corporation by authority of its governing body, and is within the scope of its corporate powers.

CORPORATE SECRETARY SIGNATURE AND CORPORATE SEAL

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: COLONIA ESCONDIDA PUMP STATION, PHASE I
BID DATE: SEPTEMBER 21, 2007

BID NO: 2008- 018
DEPARTMENT: ENG.

ITEM #	EST. QTY	UNITS	DESCRIPTION	C & C ROAD CONSTRUCTION, INC. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS							
				SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL
BASE BID 1 - UNIT PRICE SCHEDULE													
1	1	LS	MOBILIZATION	$60,000.00	$60,000.00	$40,000.00	$40,000.00		$0.00		$0.00		$0.00
2	1,800	LF	TRENCH SAFETY	$6.00	$10,800.00	$3.00	$5,400.00		$0.00		$0.00		$0.00
3	1	LS	TRAFFIC CONTROL	$14,000.00	$14,000.00	$12,000.00	$12,000.00		$0.00		$0.00		$0.00
4	11,900	SY	REMOVE AND DISPOSE ASPHALT, BASE AND SUBGRADE PER PLAN REQUIREMENTS	$7.00	$83,300.00	$4.00	$47,600.00		$0.00		$0.00		$0.00
5	11,900	SY	2.5" ASPHALT	$14.00	$166,600.00	$14.00	$166,600.00		$0.00		$0.00		$0.00
6	11,900	SY	5" BASE	$9.00	$107,100.00	$6.00	$71,400.00		$0.00		$0.00		$0.00
7	10,150	SY	8" CEMENT TREATED SUBGRADE	$9.00	$91,350.00	$16.00	$162,400.00		$0.00		$0.00		$0.00
8	1,750	SY	REMOVE 5" OF KICKER ROCK, GRADE AND COMPACT PER PLAN REQUIREMENTS	$10.00	$17,500.00	$4.00	$7,000.00		$0.00		$0.00		$0.00
9	705	LF	30" RCP AND FITTINGS, COMPLETE IN PLACE	$350.00	$246,750.00	$90.00	$63,450.00		$0.00		$0.00		$0.00
10	900	LF	24" UNRSTRAINED PVC PIPE WITH DI FITTINGS, COMPLETE IN PLACE	$280.00	$252,000.00	$90.00	$81,000.00		$0.00		$0.00		$0.00

APPROVED BY: MWP

CITY OF EL PASO BID TABULATION

BID TITLE: STORM 2006: COLONIA ESCONDIDA PUMP STATION, PHASE I
BID DATE: SEPTEMBER 21, 2007

BID NO: 2008-018
DEPARTMENT: ENG.

				C & C ROAD CONSTRUCTION, INC. EL PASO, TEXAS		DAN WILLIAMS COMPANY EL PASO, TEXAS							
ITEM #	EST. QTY	UNITS	DESCRIPTION	SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL	SUM OF(UNITS)	TOTAL
11	225	LF	24" RESTRAINED PVC PIPE WITH DI FITTINGS, COMPLETE IN PLACE	$300.00	$67,500.00	$150.00	$33,750.00		$0.00		$0.00		$0.00
12	1	LS	SWPP MEASURES, SILT FENCE, CONSTRUCTION ENTRANCE AND MAINTENANCE	$19,000.00	$19,000.00	$22,000.00	$22,000.00		$0.00		$0.00		$0.00
13	1	LS	PIPE LEAKAGE TESTING	$15,500.00	$15,500.00	$3,200.00	$3,200.00		$0.00		$0.00		$0.00
14	1	LS	VIDEO TAPE PROJECT	$5,000.00	$5,000.00	$2,200.00	$2,200.00		$0.00		$0.00		$0.00
15	18	EACH	WATER SERVICE LINE RELOCATION	$1,500.00	$27,000.00	$1,500.00	$27,000.00		$0.00		$0.00		$0.00
16	18	EACH	SEWER SERVICE LINE RELOCATION	$1,300.00	$23,400.00	$1,100.00	$19,800.00		$0.00		$0.00		$0.00
17	4	EACH	5' DIAMETER MANHOLE WITH COVER	$12,000.00	$48,000.00	$9,000.00	$36,000.00		$0.00		$0.00		$0.00
BASE BID SUM TOTAL (LINE ITEM #1 - # 17)					$1,254,800.00		$800,800.00		$0.00		$0.00		$0.00
BID BOND SUBMITTED				YES		YES							
AMENDMENTS ACKNOWLEDGED				NONE ISSUED		NONE ISSUED							

APPROVED BY: MWP