

CITY OF EL PASO BID TABULATION

BID TITLE:	CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014	BID NO: 2012-146
BID DATE:	March 7, 2012	DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
10	30	LF	HEADER CURB FOR EXPANSIVE SOIL (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$15.00	\$450.00	\$9.86	\$295.80	\$10.70	\$321.00
11	400	LF	STANDARD CURB (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$6.00	\$2,400.00	\$7.68	\$3,072.00	\$9.63	\$3,852.00
12	700	LF	STANDARD CURB (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$16.00	\$11,200.00	\$8.32	\$5,824.00	\$16.00	\$11,200.00
13	100	LF	TxDOT PINNED CURB (PLACEMENT) - REFER TO TxDOT FOR APPLICABLE DETAILS	\$9.00	\$900.00	\$8.96	\$896.00	\$6.42	\$642.00
14	370	LF	TxDOT PINNED CURB (REPLACEMENT) - REFER TO TxDOT FOR APPLICABLE DETAILS	\$14.00	\$5,180.00	\$9.61	\$3,555.70	\$9.63	\$3,563.10
15	80	LF	6-INCH ROLLED CURB (PLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$10.00	\$800.00	\$12.00	\$960.00	\$9.10	\$728.00
16	500	LF	6-INCH ROLLED CURB (REPLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$12.00	\$6,000.00	\$13.60	\$6,800.00	\$10.70	\$5,350.00
17	240	SF	4-INCH REINFORCED/6-INCH NON-REINFORCED CONCRETE RESIDENTIAL DRIVEWAY (PLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$4.00	\$960.00	\$5.00	\$1,200.00	\$3.75	\$900.00
18	8,000	SF	4-INCH REINFORCED/6-INCH NON-REINFORCED CONCRETE RESIDENTIAL DRIVEWAY (REPLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$5.00	\$40,000.00	\$7.02	\$56,160.00	\$4.07	\$32,560.00

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
19	350	SF	6-INCH CONCRETE COMMERCIAL DRIVEWAY (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS	\$6.00	\$2,100.00	\$5.64	\$1,974.00	\$4.82	\$1,687.00
20	8,000	SF	6-INCH CONCRETE COMMERCIAL DRIVEWAY (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS	\$9.00	\$72,000.00	\$7.02	\$56,160.00	\$6.30	\$50,400.00
21	23,000	SF	WHEELCHAIR RAMP / CURB CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) (PLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$4.00	\$92,000.00	\$4.37	\$100,510.00	\$6.42	\$147,660.00
22	14,000	SF	WHEELCHAIR RAMP / CURB CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) RE(PLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$11.00	\$154,000.00	\$6.48	\$90,720.00	\$9.10	\$127,400.00
23	40	SF	CAST IN PLACE ADA TILE (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$12.00	\$480.00	\$31.86	\$1,274.40	\$15.78	\$631.20
24	40	SF	SURFACE MOUNT ADA TILE (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$14.00	\$560.00	\$38.12	\$1,524.80	\$15.78	\$631.20
25	40	SF	WHEELCHAIR RAMP / CURB CUT WITH CONCRETE PAVERS (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$8.00	\$320.00	\$7.56	\$302.40	\$15.78	\$631.20
26	40	SF	WHEELCHAIR RAMP / CURB CUT WITH CONCRETE PAVERS (REPLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$11.00	\$440.00	\$7.99	\$319.60	\$15.78	\$631.20
27	100	SF	MEDIAN RAMP / CUT (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$11.00	\$1,100.00	\$4.48	\$448.00	\$9.63	\$963.00

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
28	600	SF	MEDIAN RAMP / CUT (REPLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$12.00	\$7,200.00	\$4.91	\$2,946.00	\$10.17	\$6,102.00
29	450	SF	DRAINAGE FLUME (PLACEMENT) - REFER TO DSC SECTION 2 FOR DETAILS	\$8.00	\$3,600.00	\$5.24	\$2,358.00	\$9.10	\$4,095.00
							CONTRACTOR'S TOTAL = \$2,358.80		
30	600	SF	DRAINAGE FLUME (REPLACEMENT) - REFER TO DSC SECTION 2 FOR DETAILS	\$9.00	\$5,400.00	\$5.89	\$3,534.00	\$9.63	\$5,778.00
31	1	PERCH	ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$143.00	\$143.00	\$113.40	\$113.40	\$80.25	\$80.25
32	50	PERCH	ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$113.00	\$5,650.00	\$135.00	\$6,750.00	\$80.25	\$4,012.50
33	20	PERCH	RETAINING ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$115.00	\$2,300.00	\$124.20	\$2,484.00	\$69.55	\$1,391.00
34	7	PERCH	RETAINING ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$110.00	\$770.00	\$135.00	\$945.00	\$69.55	\$486.85
35	1	PERCH	RED ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$160.00	\$160.00	\$145.80	\$145.80	\$187.25	\$187.25
36	1	PERCH	RED ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$185.00	\$185.00	\$158.60	\$158.60	\$187.25	\$187.25

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
37	200	SF	ROCKWALL RE-POINTING I INCLUDES PREPARATION AND CLEANING OF XISTING JOINTS AND RE-POINTING WITH COLOR MATCHED PORTLAND CEMENT MORTAR (2,500 PSI) REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$3.50	\$700.00	\$3.51	\$702.00	\$2.68	\$536.00
38	9	SF	ROCK RIP RAP (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$100.00	\$900.00	\$10.80	\$97.20	\$5.35	\$48.15
39	8	SF	ROCK RIP RAP (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$100.00	\$800.00	\$16.20	\$129.60	\$6.15	\$49.20
40	4	PERCH	ROCKWALL COLUMNS (PLACEMENT) - REFER TO DETAIL 13	\$202.00	\$808.00	\$216.00	\$864.00	\$187.25	\$749.00
41	4	PERCH	ROCKWALL COLUMNS (REPLACEMENT) - REFER TO DETAIL 13	\$225.00	\$900.00	\$324.00	\$1,296.00	\$187.25	\$749.00
42	40	SY	4 - INCH REINFORCED CONCRETE SLAB (PLACEMENT) - REFER TO DETAIL 14	\$20.00	\$800.00	\$45.09	\$1,803.60	\$24.08	\$963.20
43	40	SY	6 - INCH REINFORCED CONCRETE SLAB (PLACEMENT) - REFER TO DETAIL 14	\$23.00	\$920.00	\$52.49	\$2,099.60	\$26.22	\$1,048.80
44	9	SY	REINFORCED FOOTING FOR CONCRETE SLAB OR ROCKWALLS (PLACEMENT) - REFER TO DETAIL 14 FOR THE SUM OF:	\$44.00	\$396.00	\$362.88	\$3,265.92	\$53.50	\$481.50
45	1	EACH	CONCRETE BUS PAD W / APPROACH CONCRETE PAD (PLACEMENT) - REFER TO THE DSC SECTION 3 FOR CONSTRUCTION DETAILS	\$7,000.00	\$7,000.00	\$2,808.00	\$2,808.00	\$6,420.00	\$6,420.00

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
46	80	SY	8 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17	\$80.00	\$6,400.00	\$70.79	\$5,663.20	\$72.36	\$5,788.80
47	570	SY	8 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17	\$102.00	\$58,140.00	\$78.41	\$44,693.70	\$74.90	\$42,693.00
48	50	SY	10 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17	\$83.00	\$4,150.00	\$78.19	\$3,909.50	\$92.39	\$4,619.50
49	100	SY	10 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17	\$120.00	\$12,000.00	\$87.70	\$8,770.00	\$96.30	\$9,630.00
50	150	SY	12 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17	\$85.00	\$12,750.00	\$85.54	\$12,831.00	\$96.30	\$14,445.00
51	50	SY	12 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17	\$106.00	\$5,300.00	\$96.98	\$4,849.00	\$101.65	\$5,082.50
52	2	CY	JERSEY BARRIER, DECORATIVE, FLUTED, REINFORCED CONCRETE STRUCTURE (PLACEMENT) - INCLUDES REQUIRED FORMING, REINFORCED CONCRETE PLACEMENT AND REBAR FOR THE SUM OF:	\$600.00	\$1,200.00	\$1,620.00	\$3,240.00	\$267.50	\$535.00
53	2	CY	JERSEY BARRIER, DECORATIVE, FLUTED, REINFORCED CONCRETE STRUCTURE (REPLACEMENT) - INCLUDES REQUIRED FORMING, REINFORCED CONCRETE PLACEMENT AND REBAR FOR THE SUM OF:	\$420.00	\$840.00	\$2,700.00	\$5,400.00	\$267.50	\$535.00
54	4	CY	MISCELLANEOUS REINFORCED CONCRETE STRUCTURE (DRAINAGE INLETS AND OUTLETS, MANHOLES) REPAIR (PLACEMENT) - REFERENCE THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION SECTION 2 FOR CONSTRUCTION DETAILS	\$450.00	\$1,800.00	\$864.00	\$3,456.00	\$267.50	\$1,070.00

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
55	20	CY	MISCELLANEOUS REINFORCED CONCRETE STRUCTURE (DRAINAGE INLETS AND OUTLETS, MANHOLES) REPAIR (REPLACEMENT) - REFERENCE THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION SECTION 2 FOR CONSTRUCTION DETAILS	\$600.00	\$12,000.00	\$972.00	\$19,440.00	\$321.00	\$6,420.00
56	20	SY	CONCRETE CHANNEL LINING (PLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS	\$30.00	\$600.00	\$58.29	\$1,165.80	\$31.03	\$620.60
57	20	SY	CONCRETE CHANNEL LINING (REPLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS	\$60.00	\$1,200.00	\$65.99	\$1,319.80	\$34.24	\$684.80
58	2	CY	8-INCH REINFORCED RETAINING CONCRETE WALL (PLACEMENT) - TO INCLUDE REQUIRED FORMING, REBAR, AND FOOTING. FOOTING NOT PAID AS A SEPARATE LINE ITEM. SEE DETAIL 21	\$460.00	\$920.00	\$648.00	\$1,296.00	\$187.25	\$374.50
59	2	CY	8-INCH REINFORCED RETAINING CONCRETE WALL (REPLACEMENT) - TO INCLUDE REQUIRED FORMING, REBAR, AND FOOTING. FOOTING NOT PAID AS A SEPARATE LINE ITEM. SEE DETAIL 21	\$470.00	\$940.00	\$1,080.00	\$2,160.00	\$240.75	\$481.50
60	120	SY	ADD EXPOSED AGGREGATE TEXTURE FINISH USING 3/4-INCH MAX RIVER ROC	\$5.00	\$600.00	\$4.32	\$518.40	\$4.82	\$578.40
61	300	SY	ADD CONCRETE INTEGRATED COLOR TINT	\$10.00	\$3,000.00	\$27.00	\$8,100.00	\$6.96	\$2,088.00
62	40	SF	WROUGHT IRON GATE, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$9.00	\$360.00	\$9.72	\$388.80	\$8.03	\$321.20
63	40	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$10.00	\$400.00	\$10.80	\$432.00	\$8.03	\$321.20

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

			J.A.R. CONSTRUCTION, INC. EL PASO, TX			BLAIR - HALL CO., INC. EL PASO, TX			GARCOM INC. EL PASO, TX
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
64	40	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$8.00	\$320.00	\$9.72	\$388.80	\$8.03	\$321.20
65	40	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$11.00	\$440.00	\$10.80	\$432.00	\$8.03	\$321.20
66	250	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT WITH 1 FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$7.00	\$1,750.00	\$4.50	\$1,125.00	\$5.35	\$1,337.50
67	40	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT WITH 1 FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$12.00	\$480.00	\$4.50	\$180.00	\$5.35	\$214.00
68	40	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT, (PLACEMENT) - ITEM PAID BASE ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$12.00	\$480.00	\$4.50	\$180.00	\$4.28	\$171.20
69	40	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT, (REPLACEMENT) - ITEM PAID BASE ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$12.00	\$480.00	\$4.50	\$180.00	\$4.28	\$171.20
70	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT WITH 1-FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$11.00	\$440.00	\$9.01	\$360.40	\$7.49	\$299.60
71	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT WITH 1-FOOT [3-STRAND] BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$14.00	\$560.00	\$9.01	\$360.40	\$7.49	\$299.60
72	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT, (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$12.00	\$480.00	\$9.01	\$360.40	\$7.49	\$299.60

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
73	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT, (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FAVRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$14.00	\$560.00	\$9.01	\$360.40	\$7.49	\$299.60
74	15	EACH	PARKING METER PIPE (PLACEMENT) - INCLUDES FAVRICATION AND INSTALLATION OF PIPE, SAW-CUTS, CORING, CONCRETE PLACEMENT AND MATCHING TO EXISTING SURFACE FINISH. SEE DETAIL	\$160.00	\$2,400.00	\$1,296.00	\$19,440.00	\$80.25	\$1,203.75
75	2	EACH	PARKING METER PIPE (REPLACEMENT) - INCLUDES FAVRICATION AND INSTALLATION OF PIPE, SAW-CUTS, CORING, CONCRETE PLACEMENT AND MATCHING TO EXISTING SURFACE FINISH. SEE DETAIL	\$150.00	\$300.00	\$17.28	\$34.56	\$80.25	\$160.50
							CONTRACTOR'S TOTAL = \$3,456.00		
76	10	EACH	PARKING METERS PIPE BASE PLATE MOUNT (PLACEMENT) - INCLUDES BOLT PLATE AND INSTALLATION. SEE DETAIL 25	\$130.00	\$1,300.00	\$324.00	\$3,240.00	\$85.60	\$856.00
77	6	EACH	PARKING METERS PIPE BASE PLATE MOUNT (REPLACEMENT) - INCLUDES BOLT PLATE AND INSTALLATION. SEE DETAIL 25	\$130.00	\$780.00	\$864.00	\$5,184.00	\$85.60	\$513.60
78	280	SY	4-INCH REINFORCED STAMPED COLORED CONCRETE (PLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	\$39.00	\$10,920.00	\$74.30	\$20,804.00	\$38.52	\$10,785.60
79	45	SY	4-INCH REINFORCED STAMPED COLORED CONCRETE (REPLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	\$63.00	\$2,835.00	\$81.92	\$3,686.40	\$42.80	\$1,926.00

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
80	1,300	SY	6-INCH REINFORCED STAMPED COLORED CONCRETE (PLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	\$49.00	\$63,700.00	\$86.40	\$112,320.00	\$42.80	\$55,640.00
81	530	SY	6-INCH REINFORCED STAMPED COLORED CONCRETE (REPLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	\$62.00	\$32,860.00	\$93.58	\$49,597.40	\$47.08	\$24,952.40
82	1	EACH	CITY MONUMENTS (PLACEMENT) - INSTALLATION WILL INCLUDE CONCRETE BASE, CITY MONUMENT, MONUMENT HOUSING AND LID. A LICENSED SURVEYOR MUST SET THE MONUMENT AND PROVIDE ELEVATION CERTIFICAITON. REFER TO THE DSC SECTION 3 FOR DETAILS	\$600.00	\$600.00	\$1,080.00	\$1,080.00	\$535.00	\$535.00
83	15	SY	CONVETE PAVERS (REPLACEMENT) - SEE THE DETAIL 28 AT THE END OF THIS SECTION	\$74.00	\$1,110.00	\$108.00	\$1,620.00	\$42.80	\$642.00
84	5	EACH	6-INCH REINFORCED CONCRETE APRON, (PLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION	\$200.00	\$1,000.00	\$2,106.00	\$10,530.00	\$187.25	\$936.25
85	60	EACH	ADJUSTMENT OF MANHOLES - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS	\$210.00	\$12,600.00	\$648.00	\$38,880.00	\$246.10	\$14,766.00
86	10	CY	TWO- SACK BACKFILL	\$100.00	\$1,000.00	\$216.00	\$2,160.00	\$101.65	\$1,016.50
SUM TOTAL - BASE BID I (ITEMS 1-86)				\$1,866,917.00		\$2,898,102.18		\$1,991,589.95	
						CONTRACTOR'S TOTAL = \$2,901,523.62			

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
1	14,000	LF	PVC CONDUIT 3-INCH INSTALLED BY TRENCHING TO INCLUDE, SAWCUT, EXCAVATION, BACKFILL COMPACTION, PAVEMENT REMOVAL & PATCHING, JAND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$8.25	\$115,500.00	\$16.56	\$231,840.00	\$15.50	\$217,000.00
2	65,000	LF	PVC CONDUIT 2-INCH INSTALLED BY TRENCHING TO INCLUDE, SAWCUT, EXCAVATION, BACKFILL COMPACTION, PAVEMENT REMOVAL & PATCHING, JAND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$5.00	\$325,000.00	\$8.63	\$560,950.00	\$8.50	\$552,500.00
3	10,000	LF	PVC CONDUIT 3-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$20.00	\$200,000.00	\$34.16	\$341,600.00	\$32.78	\$327,800.00
4	9,000	LF	PVC CONDUIT 2-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$13.00	\$117,000.00	\$30.81	\$277,290.00	\$28.97	\$260,730.00
5	340	EACH	GROUND BOX TYPE A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$540.00	\$183,600.00	\$574.43	\$195,306.20	\$582.75	\$198,135.00
6	100	EACH	GROUND BOX TYPE C INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$500.00	\$50,000.00	\$681.03	\$68,103.00	\$690.90	\$69,090.00
7	80	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 24A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$605.00	\$48,400.00	\$828.00	\$66,240.00	\$837.90	\$67,032.00
8	190	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 30A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$1,100.00	\$209,000.00	\$1,345.50	\$255,645.00	\$1,317.75	\$250,372.50
9	30	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 36A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$1,300.00	\$39,000.00	\$1,345.50	\$40,365.00	\$1,371.30	\$41,139.00

CITY OF EL PASO BID TABULATION

BID TITLE:	CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014	BID NO: 2012-146
BID DATE:	March 7, 2012	DEPARTMENT: EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
10	30	EACH	FOUNDATION, TRAFFIC CONTROLLER INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$800.00	\$24,000.00	\$724.50	\$21,735.00	\$733.95	\$22,018.50
11	40	EACH	GROUND BOX TYPE A REPLACEMENT: TO INCLUDE, NEW TYPE A GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$600.00	\$24,000.00	\$621.00	\$24,840.00	\$637.35	\$25,494.00
12	5	EACH	GROUND BOX TYPE C REPLACEMENT: TO INCLUDE, NEW TYPE C GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$700.00	\$3,500.00	\$828.00	\$4,140.00	\$913.50	\$4,567.50
13	5	EACH	GROUND BOX TYPE 1 REPLACEMENT: TO INCLUDE, NEW TYPE 1 GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$1,100.00	\$5,500.00	\$2,691.00	\$13,455.00	\$2,677.50	\$13,387.50
14	1,000	LF	PVC CONDUIT 4-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$24.00	\$24,000.00	\$46.58	\$46,580.00	\$42.53	\$42,530.00
15	1,000	LF	PVC CONDUIT 4-INCH INSTALLED BY TRENCHING: TO INCLUDE, SAW CUT, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$7.00	\$7,000.00	\$20.70	\$20,700.00	\$15.75	\$15,750.00
SUM TOTAL - BASE BID II (ITEMS 1-15)				\$1,375,500.00		\$2,168,789.20		\$2,107,546.00	

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014 **BID NO:** 2012-146
BID DATE: March 7, 2012 **DEPARTMENT:** EPDOT

				J.A.R. CONSTRUCTION, INC. EL PASO, TX		BLAIR - HALL CO., INC. EL PASO, TX		GARCOM INC. EL PASO, TX	
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
SUM TOTAL - BASE BID I AND BASE BID II				\$3,242,417.00		\$5,066,891.38		\$4,099,135.95	
						CONTRACTOR'S TOTAL = \$5,070,312.82			
OPTION TO EXTEND THE TERM OF AGREEMENT SEVEN HUNDRED THIRTY (730) DAY ADDITIONAL TERM.				YES		NO		NO	
AMENDMENT NO. 1 ACKNOWLEDGED				YES		YES		YES	
BID BOND				YES		YES		YES	

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

			BEACON SERVICES EL PASO, TX			MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX		
--	--	--	--	--	--	---	--	--

ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
--------	----------	-------	-------------	------------	-------	------------	-------	--	--

BASE BID I - UNIT PRICE SCHEDULE

1	148,000	SF	4-INCH SIDEWALK (PLACEMENT) - REFER TO THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION (DSC) SECTION 6 FOR DETAILS	\$1.88	\$278,240.00 CONTRACTOR'S TOTAL = \$278,324.95	\$2.50	\$370,000.00		
2	205,000	SF	4-INCH SIDEWALK (REPLACEMENT) - REFER TO THE SDC SECTION 6 FOR DETAILS	\$3.41	\$699,050.00 CONTRACTOR'S TOTAL = \$699,962.25	\$5.00	\$1,025,000.00		
3	27,000	SF	4-INCH SIDEWALK REINFORCED/6-INCH NON-REINFORCED (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS	\$2.89	\$78,030.00 CONTRACTOR'S TOTAL = \$78,007.05	\$3.60	\$97,200.00		
4	22,000	SF	4-INCH SIDEWALK REINFORCED/6-INCH NON-REINFORCED (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS	\$3.68	\$80,960.00 CONTRACTOR'S TOTAL = \$80,896.20	\$5.50	\$121,000.00		
5	6,000	SF	6-INCH CONCRETE STEM-WALLS (PLACEMENT) - REFER TO DETAIL NO. 3	\$6.30	\$37,800.00 CONTRACTOR'S TOTAL = \$37,821.60	\$7.00	\$42,000.00		
6	170	LF	6-INCH CONCRETE STEM-WALL (REPLACEMENT) - REFER TO DETAIL NO. 3	\$8.40	\$1,428.00 CONTRACTOR'S TOTAL = \$1,428.82	\$8.50	\$1,445.00		
7	150	LF	CURB AND GUTTER (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$6.30	\$945.00 CONTRACTOR'S TOTAL = \$945.54	\$9.00	\$1,350.00		
8	7,800	LF	CURB AND GUTTER (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE	\$15.76	\$122,928.00 CONTRACTOR'S TOTAL = \$122,920.20	\$19.00	\$148,200.00		
9	500	LF	HEADER CURB FOR EXPANSIVE SOIL (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$6.30	\$3,150.00 CONTRACTOR'S TOTAL = \$3,151.80	\$7.00	\$3,500.00		

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, L.L.C. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
10	30	LF	HEADER CURB FOR EXPANSIVE SOIL (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$5.25	\$157.50	\$15.00	\$450.00		
					CONTRACTOR'S TOTAL = \$157.59				
11	400	LF	STANDARD CURB (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$5.25	\$2,100.00	\$6.00	\$2,400.00		
					CONTRACTOR'S TOTAL = \$2,101.20				
12	700	LF	STANDARD CURB (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$15.71	\$10,997.00	\$20.00	\$14,000.00		
					CONTRACTOR'S TOTAL = \$10,994.53				
13	100	LF	TxDOT PINNED CURB (PLACEMENT) - REFER TO TxDOT FOR APPLICABLE DETAILS	\$6.30	\$630.00	\$10.00	\$1,000.00		
					CONTRACTOR'S TOTAL = \$630.36				
14	370	LF	TxDOT PINNED CURB (REPLACEMENT) - REFER TO TxDOT FOR APPLICABLE DETAILS	\$8.40	\$3,108.00	\$14.20	\$5,254.00		
					CONTRACTOR'S TOTAL = \$3,109.78				
15	80	LF	6-INCH ROLLED CURB (PLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$6.30	\$504.00	\$8.00	\$640.00		
					CONTRACTOR'S TOTAL = \$504.29				
16	500	LF	6-INCH ROLLED CURB (REPLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$8.40	\$4,200.00	\$10.00	\$5,000.00		
					CONTRACTOR'S TOTAL = \$4,202.40				
17	240	SF	4-INCH REINFORCED/6-INCH NON-REINFORCED CONCRETE RESIDENTIAL DRIVEWAY (PLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$3.15	\$756.00	\$4.50	\$1,080.00		
					CONTRACTOR'S TOTAL = \$756.43				
18	8,000	SF	4-INCH REINFORCED/6-INCH NON-REINFORCED CONCRETE RESIDENTIAL DRIVEWAY (REPLACEMENT) - REFER THE DSC SECTION 6 FOR APPLICABLE DETAILS	\$3.68	\$29,440.00	\$5.45	\$43,600.00		
					CONTRACTOR'S TOTAL = \$29,416.80				

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
19	350	SF	6-INCH CONCRETE COMMERCIAL DRIVEWAY (PLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS	3.15	\$1,102.50	4.50	\$1,575.00		
					CONTRACTOR'S TOTAL = \$1,103.13				
20	8,000	SF	6-INCH CONCRETE COMMERCIAL DRIVEWAY (REPLACEMENT) - REFER TO THE DSC SECTION 6 FOR DETAILS	4.20	\$33,600.00	5.75	\$46,000.00		
					CONTRACTOR'S TOTAL = \$33,619.20				
21	23,000	SF	WHEELCHAIR RAMP / CURB CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) (PLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	5.25	\$120,750.00	7.60	\$174,800.00		
					CONTRACTOR'S TOTAL = \$120,819.00				
22	14,000	SF	WHEELCHAIR RAMP / CURB CUT - INCLUSIVE OF TACTILE/DETECTIBLE WARNING SURFACE "DOMES/TILE(S) RE(PLACEMENT) - REFER TO DSC SECTION 6 AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	7.35	\$102,900.00	10.50	\$147,000.00		
					CONTRACTOR'S TOTAL = \$102,958.80				
23	40	SF	CAST IN PLACE ADA TILE (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	15.50	\$620.00	40.00	\$1,600.00		
					CONTRACTOR'S TOTAL = \$619.85				
24	40	SF	SURFACE MOUNT ADA TILE (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	15.50	\$620.00	40.00	\$1,600.00		
					CONTRACTOR'S TOTAL = \$619.85				
25	40	SF	WHEELCHAIR RAMP / CURB CUT WITH CONCRETE PAVERS (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	10.51	\$420.40	12.00	\$480.00		
					CONTRACTOR'S TOTAL = \$420.24				
26	40	SF	WHEELCHAIR RAMP / CURB CUT WITH CONCRETE PAVERS (REPLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	13.66	\$546.40	20.00	\$800.00		
					CONTRACTOR'S TOTAL = \$546.31				
27	100	SF	MEDIAN RAMP / CUT (PLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	7.35	\$735.00	9.00	\$900.00		
					CONTRACTOR'S TOTAL = \$735.42				

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
28	600	SF	MEDIAN RAMP / CUT (REPLACEMENT) - REFER TO DSC SECTION 6, AND SECTION 0264 OF THESE SPECIFICATIONS FOR DETAILS	\$11.56	\$6,936.00	\$12.00	\$7,200.00		
					CONTRACTOR'S TOTAL = \$6,933.96				
29	450	SF	DRAINAGE FLUME (PLACEMENT) - REFER TO DSC SECTION 2 FOR DETAILS	\$5.25	\$2,362.50	\$8.00	\$3,600.00		
					CONTRACTOR'S TOTAL = \$2,363.85				
30	600	SF	DRAINAGE FLUME (REPLACEMENT) - REFER TO DSC SECTION 2 FOR DETAILS	\$8.40	\$5,040.00	\$10.50	\$6,300.00		
					CONTRACTOR'S TOTAL = \$5,042.88				
31	1	PERCH	ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$68.29	\$68.29	\$130.00	\$130.00		
32	50	PERCH	ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$70.39	\$3,519.50	\$150.00	\$7,500.00		
					CONTRACTOR'S TOTAL = \$3,519.51				
33	20	PERCH	RETAINING ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$68.29	\$1,365.80	\$140.00	\$2,800.00		
					CONTRACTOR'S TOTAL = \$1,365.78				
34	7	PERCH	RETAINING ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$68.29	\$478.03	\$175.00	\$1,225.00		
					CONTRACTOR'S TOTAL = \$478.02				
35	1	PERCH	RED ROCKWALL (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$178.60	\$178.60	\$200.00	\$200.00		
36	1	PERCH	RED ROCKWALL (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$178.60	\$178.60	\$300.00	\$300.00		

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
37	200	SF	ROCKWALL RE-POINTING I INCLUDES PREPARATION AND CLEANING OF XISTING JOINTS AND RE-POINTING WITH COLOR MATCHED PORTLAND CEMENT MORTAR (2,500 PSI) REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$2.63	\$526.00	\$7.00	\$1,400.00		
					CONTRACTOR'S TOTAL = \$525.30				
38	9	SF	ROCK RIP RAP (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$52.53	\$472.77	\$25.00	\$225.00		
39	8	SF	ROCK RIP RAP (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$60.41	\$483.28	\$35.00	\$280.00		
40	4	PERCH	ROCKWALL COLUMNS (PLACEMENT) - REFER TO DETAIL 13	\$183.86	\$735.44	\$250.00	\$1,000.00		
					CONTRACTOR'S TOTAL = \$735.42				
41	4	PERCH	ROCKWALL COLUMNS (REPLACEMENT) - REFER TO DETAIL 13	\$183.86	\$735.44	\$250.00	\$1,000.00		
					CONTRACTOR'S TOTAL = \$735.42				
42	40	SY	4 - INCH REINFORCED CONCRETE SLAB (PLACEMENT) - REFER TO DETAIL 14	\$14.71	\$588.40	\$40.00	\$1,600.00		
					CONTRACTOR'S TOTAL = \$588.34				
43	40	SY	6 - INCH REINFORCED CONCRETE SLAB (PLACEMENT) - REFER TO DETAIL 14	\$18.91	\$756.40	\$50.00	\$2,000.00		
					CONTRACTOR'S TOTAL = \$756.43				
44	9	SY	REINFORCED FOOTING FOR CONCRETE SLAB OR ROCKWALLS (PLACEMENT) - REFER TO DETAIL 14 FOR THE SUM OF:	\$31.52	\$283.68	\$60.00	\$540.00		
					CONTRACTOR'S TOTAL = \$283.66				
45	1	EACH	CONCRETE BUS PAD W / APPROACH CONCRETE PAD (PLACEMENT) - REFER TO THE DSC SECTION 3 FOR CONSTRUCTION DETAILS	\$6,303.60	\$6,303.60	\$8,500.00	\$8,500.00		

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
46	80	SY	8 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17	\$56.73	\$4,538.40	\$70.00	\$5,600.00		
					CONTRACTOR'S TOTAL = \$4,538.59				
47	570	SY	8 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17	\$67.24	\$38,326.80	\$90.00	\$51,300.00		
					CONTRACTOR'S TOTAL = \$38,325.89				
48	50	SY	10 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17	\$63.04	\$3,152.00	\$75.00	\$3,750.00		
					CONTRACTOR'S TOTAL = \$3,151.80				
49	100	SY	10 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17	\$73.54	\$7,354.00	\$100.00	\$10,000.00		
					CONTRACTOR'S TOTAL = \$7,354.20				
50	150	SY	12 - INCH CONCRETE PAVING (PLACEMENT) - SEE DETAIL 17	\$94.55	\$14,182.50	\$85.00	\$12,750.00		
					CONTRACTOR'S TOTAL = \$14,183.10				
51	50	SY	12 - INCH CONCRETE PAVING (REPLACEMENT) - SEE DETAIL 17	\$99.81	\$4,990.50	\$110.00	\$5,500.00		
					CONTRACTOR'S TOTAL = \$4,990.35				
52	2	CY	JERSEY BARRIER, DECORATIVE, FLUTED, REINFORCED CONCRETE STRUCTURE (PLACEMENT) - INCLUDES REQUIRED FORMING, REINFORCED CONCRETE PLACEMENT AND REBAR FOR THE SUM OF:	\$210.12	\$420.24	\$600.00	\$1,200.00		
53	2	CY	JERSEY BARRIER, DECORATIVE, FLUTED, REINFORCED CONCRETE STRUCTURE (REPLACEMENT) - INCLUDES REQUIRED FORMING, REINFORCED CONCRETE PLACEMENT AND REBAR FOR THE SUM OF:	\$210.12	\$420.24	\$750.00	\$1,500.00		
54	4	CY	MISCELLANEOUS REINFORCED CONCRETE STRUCTURE (DRAINAGE INLETS AND OUTLETS, MANHOLES) REPAIR (PLACEMENT) - REFERENCE THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION SECTION 2 FOR CONSTRUCTION DETAILS	\$262.65	\$1,050.60	\$400.00	\$1,600.00		

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
55	20	CY	MISCELLANEOUS REINFORCED CONCRETE STRUCTURE (DRAINAGE INLETS AND OUTLETS, MANHOLES) REPAIR (REPLACEMENT) - REFERENCE THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION SECTION 2 FOR CONSTRUCTION DETAILS	\$315.18	\$6,303.60	\$500.00	\$10,000.00		
56	20	SY	CONCRETE CHANNEL LINING (PLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS	\$30.47	\$609.40	\$40.00	\$800.00		
					CONTRACTOR'S TOTAL = \$609.35				
57	20	SY	CONCRETE CHANNEL LINING (REPLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS	\$33.62	\$672.40	\$50.00	\$1,000.00		
					CONTRACTOR'S TOTAL = \$672.38				
58	2	CY	8-INCH REINFORCED RETAINING CONCRETE WALL (PLACEMENT) - TO INCLUDE REQUIRED FORMING, REBAR, AND FOOTING. FOOTING NOT PAID AS A SEPARATE LINE ITEM. SEE DETAIL 21	\$183.86	\$367.72	\$300.00	\$600.00		
					CONTRACTOR'S TOTAL = \$367.71				
59	2	CY	8-INCH REINFORCED RETAINING CONCRETE WALL (REPLACEMENT) - TO INCLUDE REQUIRED FORMING, REBAR, AND FOOTING. FOOTING NOT PAID AS A SEPARATE LINE ITEM. SEE DETAIL 21	\$236.39	\$472.78	\$500.00	\$1,000.00		
					CONTRACTOR'S TOTAL = \$472.77				
60	120	SY	ADD EXPOSED AGGREGATE TEXTURE FINISH USING 3/4-INCH MAX RIVER ROC	\$4.73	\$567.60	\$8.00	\$960.00		
					CONTRACTOR'S TOTAL = \$567.32				
61	300	SY	ADD CONCRETE INTEGRATED COLOR TINT	\$6.83	\$2,049.00	\$10.00	\$3,000.00		
					CONTRACTOR'S TOTAL = \$2,048.67				
62	40	SF	WROUGHT IRON GATE, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$7.88	\$315.20	\$15.00	\$600.00		
					CONTRACTOR'S TOTAL = \$315.18				
63	40	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	\$7.88	\$315.20	\$17.00	\$680.00		
					CONTRACTOR'S TOTAL = \$315.18				

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
64	40	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (PLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	7.88	\$315.20	15.00	\$600.00		
					CONTRACTOR'S TOTAL = \$315.18				
65	40	SF	WROUGHT IRON FENCING, VARIABLE HEIGHT, (REPLACEMENT) - REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	7.88	\$315.20	18.00	\$720.00		
					CONTRACTOR'S TOTAL = \$315.18				
66	250	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT WITH 1 FOOT (3-STRAND) BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	4.20	\$1,050.00	9.00	\$2,250.00		
					CONTRACTOR'S TOTAL = \$1,050.60				
67	40	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT WITH 1 FOOT (3-STRAND) BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	4.20	\$168.00	12.00	\$480.00		
					CONTRACTOR'S TOTAL = \$168.10				
68	40	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT, (PLACEMENT) - ITEM PAID BASE ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	3.68	\$147.20	10.00	\$400.00		
					CONTRACTOR'S TOTAL = \$147.08				
69	40	SF	CHAIN-LINK FENCE, VARIABLE HEIGHT, (REPLACEMENT) - ITEM PAID BASE ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	3.68	\$147.20	15.00	\$600.00		
					CONTRACTOR'S TOTAL = \$147.08				
70	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT WITH 1-FOOT (3-STRAND) BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	7.35	\$294.00	15.00	\$600.00		
					CONTRACTOR'S TOTAL = \$294.12				
71	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT WITH 1-FOOT (3-STRAND) BARBED WIRE EXTENSION ABOVE CHAIN-LINK FENCE (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	7.35	\$294.00	18.00	\$720.00		
					CONTRACTOR'S TOTAL = \$294.17				
72	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT, (PLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FABRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	7.35	\$294.00	13.00	\$520.00		
					CONTRACTOR'S TOTAL = \$294.17				

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
73	40	SF	CHAIN-LINK FENCE, SWINGING GATE, VARIABLE HEIGHT, (REPLACEMENT) - ITEM PAID BASED ON NET AREA OF INSTALLED METAL FAVRIC. REFER TO THE DSC SECTION 4 FOR CONSTRUCTION DETAILS	77.35	\$294.00	18.00	720.00		
					CONTRACTOR'S TOTAL = \$294.17				
74	15	EACH	PARKING METER PIPE (PLACEMENT) - INCLUDES FAVRICATION AND INSTALLATION OF PIPE, SAW-CUTS, CORING, CONCRETE PLACEMENT AND MATCHING TO EXISTING SURFACE FINISH. SEE DETAIL	78.80	\$1,182.00	100.00	1,500.00		
					CONTRACTOR'S TOTAL = \$1,181.93				
75	2	EACH	PARKING METER PIPE (REPLACEMENT) - INCLUDES FAVRICATION AND INSTALLATION OF PIPE, SAW-CUTS, CORING, CONCRETE PLACEMENT AND MATCHING TO EXISTING SURFACE FINISH. SEE DETAIL	78.80	\$157.60	250.00	500.00		
					CONTRACTOR'S TOTAL = \$157.59				
76	10	EACH	PARKING METERS PIPE BASE PLATE MOUNT (PLACEMENT) - INCLUDES BOLT PLATE AND INSTALLATION. SEE DETAIL 25	84.05	\$840.50	100.00	1,000.00		
					CONTRACTOR'S TOTAL = \$840.48				
77	6	EACH	PARKING METERS PIPE BASE PLATE MOUNT (REPLACEMENT) - INCLUDES BOLT PLATE AND INSTALLATION. SEE DETAIL 25	84.05	\$504.30	125.00	750.00		
					CONTRACTOR'S TOTAL = \$504.29				
78	280	SY	4-INCH REINFORCED STAMPED COLORED CONCRETE (PLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	37.82	\$10,589.60	46.00	12,880.00		
					CONTRACTOR'S TOTAL = \$10,590.05				
79	45	SY	4-INCH REINFORCED STAMPED COLORED CONCRETE (REPLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	42.02	\$1,890.90	65.00	2,925.00		
					CONTRACTOR'S TOTAL = \$1,891.08				

CITY OF EL PASO BID TABULATION

BID TITLE:	CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014	BID NO: 2012-146
BID DATE:	March 7, 2012	DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
80	1,300	SY	6-INCH REINFORCED STAMPED COLORED CONCRETE (PLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER, BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	\$42.02	\$54,626.00 CONTRACTOR'S TOTAL = \$54,631.20	\$48.00	\$62,400.00		
81	530	SY	6-INCH REINFORCED STAMPED COLORED CONCRETE (REPLACEMENT) - INCLUDES A MINIMUM OF THREE STAMP PATTERNS, COLOR TINT AND APPLICATION OF TINT AND SEALER. BOTH POWDER AND LIQUID RELEASE AGENT REQUIRED DEPENDING ON THE APPLICATION. COLOR MATCH ADJACENT CONCRETE OR AS DIRECTED BY INSPECTOR. SE TECHNICAL SPECIFICATIONS, DIVISION III, ITEM 5326	\$46.23	\$24,501.90 CONTRACTOR'S TOTAL = \$24,499.99	\$62.00	\$32,860.00		
82	1	EACH	CITY MONUMENTS (PLACEMENT) - INSTALLATION WILL INCLUDE CONCRETE BASE, CITY MONUMENT, MONUMENT HOUSING AND LID. A LICENSED SURVEYOR MUST SET THE MONUMENT AND PROVIDE ELEVATION CERTIFICATION. REFER TO THE DSC SECTION 3 FOR DETAILS	\$525.30	\$525.30	\$1,000.00	\$1,000.00		
83	15	SY	CONCRETE PAVERS (REPLACEMENT) - SEE THE DETAIL 28 AT THE END OF THIS SECTION	\$42.02	\$630.30 CONTRACTOR'S TOTAL = \$630.36	\$65.00	\$975.00		
84	5	EACH	6-INCH REINFORCED CONCRETE APRON, (PLACEMENT) - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION	\$183.86	\$919.30 CONTRACTOR'S TOTAL = \$919.28	\$275.00	\$1,375.00		
85	60	EACH	ADJUSTMENT OF MANHOLES - REFER TO THE DSC SECTION 2 FOR CONSTRUCTION DETAILS	\$199.61	\$11,976.60 CONTRACTOR'S TOTAL = \$11,976.84	\$180.00	\$10,800.00		
86	10	CY	TWO- SACK BACKFILL	\$94.55	\$945.50 CONTRACTOR'S TOTAL = \$945.54	\$110.00	\$1,100.00		
SUM TOTAL - BASE BID I (ITEMS 1-86)				\$1,845,446.91		\$2,553,189.00			
					CONTRACTOR'S TOTAL = \$1,846,508.30				

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
1	14,000	LF	PVC CONDUIT 3-INCH INSTALLED BY TRENCHING TO INCLUDE, SAWCUT, EXCAVATION, BACKFILL COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$16.54	\$231,560.00	\$10.40	\$145,600.00		
					CONTRACTOR'S TOTAL = \$231,510.22				
2	65,000	LF	PVC CONDUIT 2-INCH INSTALLED BY TRENCHING TO INCLUDE, SAWCUT, EXCAVATION, BACKFILL COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$13.69	\$889,850.00	\$9.05	\$588,250.00		
					CONTRACTOR'S TOTAL = \$889,805.67				
3	10,000	LF	PVC CONDUIT 3-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$25.80	\$258,000.00	\$28.00	\$280,000.00		
					CONTRACTOR'S TOTAL = \$258,027.36				
4	9,000	LF	PVC CONDUIT 2-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$22.06	\$198,540.00	\$22.00	\$198,000.00		
					CONTRACTOR'S TOTAL = \$198,563.40				
5	340	EACH	GROUND BOX TYPE A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$790.05	\$268,617.00	\$448.00	\$152,320.00		
					CONTRACTOR'S TOTAL = \$268,617.41				
6	100	EACH	GROUND BOX TYPE C INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$963.40	\$96,340.00	\$590.00	\$59,000.00		
					CONTRACTOR'S TOTAL = \$96,340.02				
7	80	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 24A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$567.32	\$45,385.60	\$500.00	\$40,000.00		
					CONTRACTOR'S TOTAL = \$45,385.92				
8	190	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 30A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS; FOR THE SUM OF:	\$693.40	\$131,746.00	\$900.00	\$171,000.00		
					CONTRACTOR'S TOTAL = \$131,745.24				
9	30	EACH	FOUNDATION, TRAFFIC SIGNAL TYPE 36A INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$819.47	\$24,584.10	\$1,100.00	\$33,000.00		
					CONTRACTOR'S TOTAL = \$24,584.04				

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
10	30	EACH	FOUNDATION, TRAFFIC CONTROLLER INSTALLED IN PLACE: TO INCLUDE, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$2,206.26	\$66,187.80	\$740.00	\$22,200.00		
11	40	EACH	GROUND BOX TYPE A REPLACEMENT: TO INCLUDE, NEW TYPE A GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$950.79	\$38,031.60	\$505.00	\$20,200.00		
					CONTRACTOR'S TOTAL = \$138,031.72				
12	5	EACH	GROUND BOX TYPE C REPLACEMENT: TO INCLUDE, NEW TYPE C GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$1,192.43	\$5,962.15	\$650.00	\$3,250.00		
					CONTRACTOR'S TOTAL = \$5,962.16				
13	5	EACH	GROUND BOX TYPE 1 REPLACEMENT: TO INCLUDE, NEW TYPE 1 GROUND BOX, REMOVAL OF OLD/BROKEN BOX AND INSTALLATION OF NEW GROUND BOX, SAW CUT, LOOP SEALANT, EXCAVATION, BACKFILL, COMPACTION, CONCRETE REMOVAL, CONCRETE PLACEMENT, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$2,311.32	\$11,556.60	\$790.00	\$3,950.00		
14	1,000	LF	PVC CONDUIT 4-INCH INSTALLED BY DIRECTIONAL BORING: TO INCLUDE, BORING, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$32.57	\$32,570.00	\$37.00	\$37,000.00		
					CONTRACTOR'S TOTAL = \$32,568.60				
15	1,000	LF	PVC CONDUIT 4-INCH INSTALLED BY TRENCHING: TO INCLUDE, SAW CUT, EXCAVATION, BACKFILL, COMPACTION, PAVEMENT REMOVAL & PATCHING, AND DISPOSAL OF WASTE MATERIAL. REFERENCE DIVISION VI, "INSTALLATION OF CONDUIT, LOOPS, FOUNDATIONS, AND GROUND BOXES" SPECIFICATIONS	\$20.49	\$20,490.00	\$12.00	\$12,000.00		
					CONTRACTOR'S TOTAL = \$20,486.70				
SUM TOTAL - BASE BID II (ITEMS 1-15)				\$2,319,420.85		\$1,765,770.00			
				CONTRACTOR'S TOTAL = \$2,319,372.85					

CITY OF EL PASO BID TABULATION

BID TITLE: CITYWIDE REPAIR OR CONSTRUCTION OF PARKWAY STRUCTURES 2012-2014
BID DATE: March 7, 2012

BID NO: 2012-146
DEPARTMENT: EPDOT

				BEACON SERVICES EL PASO, TX		MARTINEZ BROS. CONTRACTORS, LLC. EL PASO, TX			
ITEM #	EST. QTY	UNITS	DESCRIPTION	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL		
SUM TOTAL - BASE BID I AND BASE BID II				\$4,164,867.76		\$4,318,959.00			
				CONTRACTOR'S TOTAL = \$4,165,881.14		CONTRACTOR'S TOTAL = \$5,070,312.82			
OPTION TO EXTEND THE TERM OF AGREEMENT SEVEN HUNDRED THIRTY (730) DAY ADDITIONAL TERM.				YES		NO			
AMENDMENT NO. 1 ACKNOWLEDGED				YES		YES			
BID BOND				YES		YES			