



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>					<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
<b>BASE BID 1 :</b>					<b>J.A.R CONCRETE INC.</b>  <b>EL PASO, TX</b>  <b>BIDDER 1 OF 5</b>		<b>J. CARRIZAL GENERAL CONSTRUCTION, INC.</b>  <b>EL PASO, TX</b>  <b>BIDDER 2 OF 5</b>		<b>KARLSRUHER INC. dba CSA CONSTRUCTORS</b>  <b>EL PASO, TX</b>  <b>BIDDER 3 OF 5</b>	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
1.	5,800	CY	SIDEWALK	Sidewalk includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, HMAC patching, site restoration, cleanup, and proper disposal of all waste materials. Reference Section 6-12 of the Design Standards for Construction (DSC)	\$240.00	\$1,392,000.00	\$270.00	\$1,566,000.00	\$280.00	\$1,624,000.00
2.	450	CY	6" STEM-WALL	6" Concrete stem-walls to include saw-cuts, excavation, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Technical Specifications Detail 3	\$279.00	\$125,550.00 Contractor's Price \$125,500	\$270.00	\$121,500.00	\$245.00	\$110,250.00
3.	3,200	CY	CURB STRUCTURE	Curb structure includes gutter if required, saw-cut, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching, backfill, cleanup, and proper disposal of waste material. Reference Sections 6-2 thru 6-6 of the DSC	\$140.00	\$448,000.00	\$144.00	\$460,800.00	\$325.00	\$1,040,000.00
4.	15	CY	TXDOT PINNED CURB	TxDOT Pinned Curb includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching cleanup and proper disposal of all waste materials, Reference Technical Specifications Detail 5	\$1,140.00	\$17,100.00	\$144.00	\$2,160.00	\$300.00	\$4,500.00
5.	1,750	CY	DRIVEWAY	Residential/Commercial Driveway includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching, cleanup and proper disposal of all waste materials. Reference Section 6-15 thru 6-18 of the DSC	\$280.00	\$490,000.00	\$297.00	\$519,750.00	\$280.00	\$490,000.00


Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016						BID NO: 2016-497					
BID DATE: JANUARY 13, 2016						DEPARTMENT: CAPITAL IMPROVEMENT					
					J.A.R CONCRETE INC.		J. CARRIZAL GENERAL CONSTRUCTION, INC.		KARLSRUHER INC. dba CSA CONSTRUCTORS		
					EL PASO, TX		EL PASO, TX		EL PASO, TX		
BASE BID I :					BIDDER 1 OF 5		BIDDER 2 OF 5		BIDDER 3 OF 5		
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
6.	875	CY	WHEELCHAIR RAMP	Wheelchair Ramp / Curb Cut includes saw-cuts, removal of existing structures, excavation, preparation and 95% compaction of subgrade, forming, concrete placement, ADA tile placement, compacted backfill, site restoration, HMAC patching, cleanup and proper disposal of all waste materials. Finished product must meet current TDLR and ADA requirements. Reference Section 0264 and Section 6-20 thru 6-30 of the DSC	\$452.00	\$395,500.00	\$297.00	\$259,875.00	\$300.00	\$262,500.00	
7.	15	CY	FLUME	Drainage Flume includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching cleanup and proper disposal of all waste materials. Reference Section 2-34 thru 2-36 of the DSC	\$540.00	\$8,100.00	\$1,755.00	\$26,325.00	\$280.00	\$4,200.00	
8.	62	PERCH	ROCKWALL	Rockwall includes excavation, preparation and compaction of foundation subgrade, reinforced concrete footing placement, wall construction, rockwall cap, site restorations, compacted backfill, cleanup and proper disposal of all waste materials. Perch paid on rock volume basis. Reference Section 4-3 of the DSC	\$173.00	\$10,726.00	\$200.00	\$12,400.00	\$150.00	\$9,300.00	
9.	7	PERCH	ROCKWALL RETAINING	Retaining Rockwall includes excavation, preparation and compaction of foundation subgrade, reinforced concrete footing placement, wall construction, rockwall cap, site restoration, compacted backfill, cleanup and proper disposal of all waste materials. Perch paid on rock volume basis. Reference Section 4-3 of the DSC	\$139.00	\$973.00	\$220.00	\$1,540.00	\$150.00	\$1,050.00	


Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM


**BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016**
**BID DATE: JANUARY 13, 2016**
**BID NO: 2016-497**
**DEPARTMENT: CAPITAL IMPROVEMENT**

BASE BID 1:					J.A.R CONCRETE INC. EL PASO, TX BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC. EL PASO, TX BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS EL PASO, TX BIDDER 3 OF 5	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
10.	32	PERCH	RED ROCKWALL	Red Rockwall includes excavation, preparation and compaction of foundation subgrade, reinforced concrete footing placement, Franklin Red Rock wall construction, rockwall cap, site restoration, compacted backfill, cleanup and proper disposal of all waste materials. Perch paid on rock volume basis. Reference Section 4-3 of the DSC	\$188.00	\$6,016.00	\$230.00	\$7,360.00	\$170.00	\$5,440.00
11.	159	SF	ROCKWALL RE-POINTING	Rockwall re-pointing: to include preparation and cleaning of existing joints, re-pointing with color matched Portland cement mortar (2,500 psi), site restoration, cleanup and proper disposal of all waste materials	\$5.00	\$795.00	\$5.50	\$874.50	\$65.00	\$10,335.00
12.	100	SF	ROCK RIP-RAP	Rock Rip Rap includes excavation, preparation and compaction of subgrade, placement of reinforced concrete footing and rock rip rap elements, site restoration, compacted backfill, cleanup and proper disposal of waste materials. Measured on a Perch Basis. Reference Section 5-2 of the DSC	\$12.50	\$1,250.00	\$20.00	\$2,000.00	\$6.00	\$600.00
13.	62	PERCH	ROCKWALL COLUMN	Rock wall columns includes excavation, preparation and compaction of foundation subgrade, placement of reinforced concrete footing and rock column elements, column cap, site restoration, compacted backfill, cleanup and proper disposal of waste materials. Measured on a Perch Basis. Reference Column Detail 13	\$348.00	\$21,576.00	\$280.00	\$17,360.00	\$175.00	\$10,850.00
14.	40	CY	CONCRETE SLAB	Reinforced Concrete Slab includes saw-cuts, excavation, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Detail 14	\$279.00	\$11,160.00	\$445.50	\$17,820.00	\$300.00	\$12,000.00


 Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016					BID NO: 2016-497					
BID DATE: JANUARY 13, 2016					DEPARTMENT: CAPITAL IMPROVEMENT					
BASE BID 1:					J.A.R CONCRETE INC. EL PASO, TX BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC. EL PASO, TX BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS EL PASO, TX BIDDER 3 OF 5	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
15.	45	CY	CONCRETE FOOTING	Footing for concrete slab includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming as required, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Detail 14	\$456.00	\$20,520.00	\$277.60	\$12,492.00	\$300.00	\$13,500.00
16.	3	EACH	CONCRETE BUS PAD	Concrete bus pad w /approach concrete pad: to include saw-cuts, excavation, preparation and compaction of subgrade, reinforced concrete placement, compacted backfill, HMAC paving, site restoration, cleanup and proper disposal of all waste materials. Reference Section 3-20 and 3-21 of the DSC	\$9,700.00	\$29,100.00	\$1,500.00	\$4,500.00	\$6,500.00	\$19,500.00
17.	165	CY	CONCRETE PAVING	Concrete paving to include saw-cuts, excavation, preparation and compaction of subgrade, reinforced concrete placement, compacted backfill, restoration, cleanup and proper disposal of all waste materials. Reference Section 3 of the DSC and technical specifications figure 43	\$352.00	\$58,080.00	\$270.00	\$44,550.00 Contractor's Price \$44,500.00	\$280.00	\$46,200.00
18.	625	CY	MISC. CONCRETE	Miscellaneous Reinforced Concrete structure [drainage inlets and outlets, manholes, barrier walls] repair includes saw-cuts, excavation, preparation and compaction of subgrade, required forming, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials	\$143.00	\$89,375.00	\$270.00	\$168,750.00	\$375.00	\$234,375.00
19.	5	CY	CONCRETE CHANNEL LINING	Concrete channel lining: to include saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming concrete placement, compacted backfill, restoration, cleanup and proper disposal of all waste materials. Reference Section 2-39 of the DSC	\$807.00	\$4,035.00	\$300.00	\$1,500.00	\$285.00	\$1,425.00

Approved By:   
Date: 1/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016						BID NO: 2016-497					
BID DATE: JANUARY 13, 2016						DEPARTMENT: CAPITAL IMPROVEMENT					
BASE BID I :					J.A.R CONCRETE INC. EL PASO, TX BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC. EL PASO, TX BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS EL PASO, TX BIDDER 3 OF 5		
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
20.	5	CY	RETAINING CONCRETE WALL	8-inch Reinforced retaining concrete wall: includes saw-cuts, excavation, preparation and compaction of subgrade, required forming, reinforced concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Technical Specifications Detail 21	\$801.00	\$4,005.00	\$405.00	\$2,025.00	\$400.00	\$2,000.00	
21.	10	SY	EXPOSED AGGREGATE	Add Exposed aggregate texture finish using 3/4-inch max river rock	\$75.00	\$750.00	\$225.00	\$2,250.00	\$15.00	\$150.00	
22.	250	SY	COLOR TINT	Add concrete integrated color tint	\$12.00	\$3,000.00	\$7.50	\$1,875.00	\$15.00	\$3,750.00	
23.	260	SF	WROUGHT IRON GATE	Wrought iron gate, variable height: to include fabrication of wrought iron gate, posts and locking device, wheels when required, paint finish, concrete footing placement, site cleanup and proper disposal of all waste materials. Reference Section 4-4 of the DSC	\$14.50	\$3,770.00	\$12.50	\$3,250.00	\$17.00	\$4,420.00	
24.	5,450	SF	WROUGHT IRON FENCE	Wrought iron fencing, variable height: to include fabrication of wrought iron gate, end and line posts, paint finish, concrete footing placement, site cleanup and proper disposal of all waste materials. Reference Section 4-4 of the DSC	\$12.70	\$69,215.00	\$12.50	\$68,125.00	\$10.00	\$54,500.00	
25.	100	SF	CHAIN-LINK FENCE	Chain-link fence, variable height, to include all materials, chain-link fence fabric, fence posts, concrete footings, cleanup, site restoration and proper disposal of all waste materials. Item to be paid based on net area of installed metal fabric. Reference Section 4-1 and 4-2 of the DSC	\$5.00	\$500.00	\$3.25	\$325.00	\$4.75	\$475.00	

Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM




**BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016**

**BID DATE: JANUARY 13, 2016**

**BID NO: 2016-497**

**DEPARTMENT: CAPITAL IMPROVEMENT**

BASE BID I:					J.A.R CONCRETE INC. EL PASO, TX BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC. EL PASO, TX BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS EL PASO, TX BIDDER 3 OF 5	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
26.	20	SF	CHAIN-LIN FENCE GATE	Chain-link fence gate, variable height, to include all materials, chain-link fence fabric, fence posts, concrete footings, wheels when required, cleanup, site restoration and proper disposal of all waste materials. Item to be paid based on net area of installed metal fabric. Reference Section 4-1 and 4-2 of the DSC	\$21.00	\$420.00	\$18.00	\$360.00	\$21.00	\$420.00
27.	55	EACH	PARKING METER PIPE	Parking Meter Pipe includes saw-cuts/coring, excavation, concrete foundation; match existing surface finish, site restoration, cleanup, and proper disposal of all waste materials. Reference detail 25	\$300.00	\$16,500.00	\$125.00	\$6,875.00	\$175.00	\$9,625.00
28.	25	EACH	PARKING METER PIPE WITH BASE PLATE MOUNT	Parking Meters Pipe Base Plate Mount includes installation of bolted plate, site restoration, cleanup, and proper disposal of all waste materials. Reference detail 25	\$209.00	\$5,225.00	\$95.00	\$2,375.00	\$200.00	\$5,000.00
29.	525	CY	STAMPED COLORED CONCRETE	Stamped colored concrete; minimum of 3 stamp patterns, color match adjacent concrete or as directed by inspector, includes saw-cuts, excavation and/or fill up to 6 inches, preparation and 95% compaction of subgrade, reinforcement (if required), concrete placement, application of 2 coats of sealer, site restoration, cleanup and proper disposal of all waste materials. Reference Technical Specifications, Division III, Item 5326	\$360.00	\$189,000.00	\$567.00	\$297,675.00	\$450.00	\$236,250.00
30.	1	EACH	6-INCH CONCRETE APRON	Installation of 6-inch reinforced concrete aprons in roadway around water valves, city monuments and manholes, includes proper elevation adjustment of valves, monument housings, manholes and concrete bells	\$900.00	\$900.00	\$675.00	\$675.00	\$150.00	\$150.00


Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM


**BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016**
**BID DATE: JANUARY 13, 2016**
**BID NO: 2016-497**
**DEPARTMENT: CAPITAL IMPROVEMENT**

BASE BID 1:					J.A.R CONCRETE INC. EL PASO, TX BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC. EL PASO, TX BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS EL PASO, TX BIDDER 3 OF 5	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
31.	20	EACH	MANHOLE ADJUSTMENT	Adjustment and level up of manhole to grade	\$260.00	\$5,200.00	\$500.00	\$10,000.00	\$250.00	\$5,000.00
32.	180	EACH	BONNET BOX ADJUSTMENT	Adjustment and level up to grade of water meter, watervalue, city monument bonnets (concrete bell) for the sum of:	\$150.00	\$27,000.00	\$800.00	\$144,000.00	\$175.00	\$31,500.00
33.	50	CY	TWO-SACK	Placement of two-sack backfill	\$105.00	\$5,250.00	\$94.00	\$4,700.00	\$110.00	\$5,500.00
34.	6,050	CY	DEMOLITION	Demolition and removal: to include concrete, asphalt, dirt, subgrade, vegetation, debris with proper disposal. Reference Technical Specifications Division II Section 0210	\$119.00	\$719,950.00	\$81.00	\$490,050.00	\$20.00	\$121,000.00
35.	2,000	Lb	REINFORCING STEEL	Provide and install steel reinforcing deformed bars conforming to ASTM A 615, Grade 60, unless noted otherwise on the drawings and/or by request	\$5.00	\$10,000.00	\$0.50	\$1,000.00	\$3.00	\$6,000.00
36.	60	DAY	TMA (24 hrs)	Special Traffic Control-Provide truck Mounted Attenuator when required	\$379.00	\$22,740.00	\$498.00	\$29,880.00	\$357.00	\$21,420.00
37.	1,000	CY	AGGREGATE BASE COURSE	Base course composed of crushed aggregates placed and compacted on the prepared subgrade to required grades	\$12.00	\$12,000.00	\$35.10	\$35,100.00	\$28.00	\$28,000.00

 Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016							BID NO: 2016-497			
BID DATE: JANUARY 13, 2016							DEPARTMENT: CAPITAL IMPROVEMENT			
					J.A.R CONCRETE INC.  EL PASO, TX  BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC.  EL PASO, TX  BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS  EL PASO, TX  BIDDER 3 OF 5	
BASE BID I :										
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
38.	1,000	CY	TOP SOIL BACKFILL	Placement of topsoil, Reference Technical Specifications Section 0220	\$9.00	\$9,000.00	\$109.75	\$109,750.00	\$25.00	\$25,000.00
39.	500	CY	STRUCTURAL BACKFILL	Placement of structural material backfill to 95% compaction, Reference Technical Specifications Section 0220	\$15.00	\$7,500.00	\$68.50	\$34,250.00	\$28.00	\$14,000.00
40.	20	EACH	TREE REMOVAL	The removal of tree various sizes ranging up to 18" caliper where required	\$550.00	\$11,000.00	\$500.00	\$10,000.00	\$500.00	\$10,000.00
41.	150,000	SF	WIRE MESH REINFORCEMENT	Provide and install Prefabricated 6" X 6", Welded Wire Fabric	\$0.20	\$30,000.00	\$0.653	\$97,950.00	\$0.50	\$75,000.00
42.	400	Hr	UTILITY LINE REPAIR	Provide for all labor, superintendence, equipment, supplies etc. to repair damaged water or gas lines and meters as required by the project due to no fault of the contractor	\$19.00	\$7,600.00	\$200.00	\$80,000.00	\$250.00	\$100,000.00
SUM TOTAL BASE BID I (1 - 42)					\$4,290,381.00		\$4,680,046.50		\$4,659,185.00	

Approved By:   
Date: 2/4/16








# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016							BID NO: 2016-497			
BID DATE: JANUARY 13, 2016							DEPARTMENT: CAPITAL IMPROVEMENT			
					J.A.R CONCRETE INC.  EL PASO, TX  BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC.  EL PASO, TX  BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS  EL PASO, TX  BIDDER 3 OF 5	
BASE BID II :										
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
5.	150	EACH	GROUND BOX TYPE A	Ground Box Type A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, concrete apron, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$401.00	\$60,150.00	\$1,250.00	\$187,500.00 Contractor's Price \$180,000.00	\$375.00	\$56,250.00
6.	25	EACH	GROUND BOX TYPE C	Ground Box Type C installed in place: to include, excavation, backfill, compaction, concrete removal & patching, concrete apron, and disposal of waste material. Reference Division VI, "installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$1,000.00	\$25,000.00	\$1,375.00	\$34,375.00	\$375.00	\$9,375.00
7.	45	EACH	FOUNDATION TRAFFIC SIGNAL TYPE 24A	Foundation, Traffic Signal Type 24A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$900.00	\$40,500.00	\$2,423.00	\$109,035.00	\$650.00	\$29,250.00
8.	115	EACH	FOUNDATION TRAFFIC SIGNAL TYPE 30A	Foundation, Traffic Signal Type 30A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$1,134.00	\$130,410.00	\$3,423.00	\$393,645.00	\$600.00	\$69,000.00


Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016					BID NO: 2016-497					
BID DATE: JANUARY 13, 2016					DEPARTMENT: CAPITAL IMPROVEMENT					
<div>BASE BID II :</div>					J.A.R CONCRETE INC.		J. CARRIZAL GENERAL CONSTRUCTION, INC.		KARLSRUHER INC. dba CSA CONSTRUCTORS	
					EL PASO, TX		EL PASO, TX		EL PASO, TX	
					BIDDER 1 OF 5		BIDDER 2 OF 5		BIDDER 3 OF 5	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
9.	2	EACH	FOUNDATION TRAFFIC SIGNAL TYPE 36A	Foundation, Traffic Signal Type 36A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations and Ground Boxes" of the Technical Specifications	\$3,000.00	\$6,000.00	\$4,223.00	\$8,446.00	\$650.00	\$1,300.00
10.	2	EACH	FOUNDATION TRAFFIC CONTROLLER	Foundation, Traffic Controller installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$1,100.00	\$2,200.00	\$3,423.00	\$6,846.00	\$650.00	\$1,300.00
11.	40	EACH	RECTANGULAR CONCRETE APRON	Installation of rectangular reinforced concrete aprons around Ground Boxes. To include proper elevation adjustment of ground boxes. Reference Technical of the Technical Specifications General Requirement for All Electrical Work Figure 34	\$250.00	\$10,000.00	\$3,281.00	\$131,240.00	\$350.00	\$14,000.00
SUM TOTAL BASE BID II (1 - 11)					\$553,197.00		\$1,980,099.50		\$439,925.00	
							Contractor's Price \$1,972,599.50			


Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016						BID NO: 2016-497					
BID DATE: JANUARY 13, 2016						DEPARTMENT: CAPITAL IMPROVEMENT					
					J.A.R CONCRETE INC.  EL PASO, TX  BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC.  EL PASO, TX  BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS  EL PASO, TX  BIDDER 3 OF 5		
BASE BID III :											
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
1.	300	EACH	4" CALIPER TREE	The installation of minimum 4" caliper tree where required	\$440.00	\$132,000.00	\$594.00	\$178,200.00	\$600.00	\$180,000.00	
2.	300	EACH	3" CALIPER TREE	The installation of minimum 3" caliper tree where required	\$330.00	\$99,000.00	\$369.00	\$110,700.00	\$300.00	\$90,000.00	
3.	300	EACH	2" CALIPER TREE	The installation of minimum 2" caliper tree where required	\$220.00	\$66,000.00	\$243.00	\$72,900.00	\$200.00	\$60,000.00	
4.	400	EACH	5 GAL. SHRUBS	The installation of minimum 5 gallon container shrub where required	\$22.00	\$8,800.00	\$20.64	\$8,256.00	\$27.00	\$10,800.00	
5.	400	EACH	1 GAL. SHRUBS	The installation of minimum one (1) gallon container groundcover where required	\$11.00	\$4,400.00	\$11.86	\$4,744.00	\$10.00	\$4,000.00	
6.	40	EACH	BACKFLOW PREVENTER	The installation of 2-inch double check backflow preventer where required	\$731.50	\$29,260.00	\$765.00	\$30,600.00	\$490.00	\$19,600.00	
7.	20	EACH	WATER PRESSURE REGULATOR	The installation of water pressure regulator bronze body or inline pressure regulator 30 PSI where required	\$148.50	\$2,970.00	\$990.00	\$19,800.00	\$750.00	\$15,000.00	
8.	20	EACH	TBOS	The installation of TBOS battery operated system where required	\$275.00	\$5,500.00	\$230.62	\$4,612.40	\$175.00	\$3,500.00	

Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



**BID TITLE:** CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016

**BID DATE:** JANUARY 13, 2016

**BID NO:** 2016-497

**DEPARTMENT:** CAPITAL IMPROVEMENT

BASE BID III :					J.A.R CONCRETE INC. EL PASO, TX BIDDER 1 OF 5		J. CARRIZAL GENERAL CONSTRUCTION, INC. EL PASO, TX BIDDER 2 OF 5		KARLSRUHER INC. dba CSA CONSTRUCTORS EL PASO, TX BIDDER 3 OF 5	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
9.	20	EACH	BOX FOR BACKFLOW	The installation of reinforced concrete box for backflow 17 inches by 30 inches with screw down steel checker lid, where required	\$377.30	\$7,546.00	\$185.62	\$3,712.40	\$375.00	\$7,500.00 Contractor's Price \$11,250.00
10.	20	EACH	REMOTE VALVE	The installation of electric remote valve with latching solenoid where required	\$181.50	\$3,630.00	\$163.12	\$3,262.40	\$135.00	\$2,700.00
11.	3,600	LF	¼ " DISTRIBUTION TUBING	The installation of ¼ inch distribution tubing where required	\$0.44	\$1,584.00	\$0.37	\$1,332.00	\$0.20	\$720.00
12.	1,200	EACH	DRIP EMITTERS	The installation of drip emitters, where required	\$55.00	\$66,000.00	\$1.29	\$1,548.00	\$0.75	\$900.00
13.	9,000	LF	SCHEDULE 40 PIPE	The installation of ¾ inch PVC pipe schedule 40 (includes excavation, backfill, all fitting) where required	\$4.13	\$37,170.00	\$1.04	\$9,360.00	\$0.55	\$4,950.00
14.	20	EACH	Y-STRAINER	The installation of Y-Strainer, where required	\$49.50	\$990.00	\$225.00	\$4,500.00	\$35.00	\$700.00
15.	9,000	LF	DRIPLINE	The installation of ¾ inch PLD dripline tubing (includes excavation, backfill, all fittings) where required	\$1.10	\$9,900.00	\$0.40	\$3,600.00	\$0.50	\$4,500.00

Approved By: 

Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016					BID NO: 2016-497					
BID DATE: JANUARY 13, 2016					DEPARTMENT: CAPITAL IMPROVEMENT					
<b>BASE BID III :</b>					<b>J.A.R CONCRETE INC.</b> EL PASO, TX BIDDER 1 OF 5		<b>J. CARRIZAL GENERAL CONSTRUCTION, INC.</b> EL PASO, TX BIDDER 2 OF 5		<b>KARLSRUHER INC. dba CSA CONSTRUCTORS</b> EL PASO, TX BIDDER 3 OF 5	
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
16.	400	CY	2" ROCK	The installation of 2" minimum size franklin red rock over landscaping weed blocking fabric material	\$94.05	\$37,620.00	\$122.02	\$48,808.00	\$48.00	\$19,200.00
17.	300	CY	4" ROCK	The installation of 4" minimum size franklin red rock over landscaping weed blocking fabric material	\$94.05	\$28,215.00	\$123.84	\$37,152.00	\$58.00	\$17,400.00
18.	200	CY	6" + ROCK	The installation of 6" minimum size river rock over landscaping weed blocking fabric material	\$267.30	\$53,460.00	\$188.64	\$37,728.00	\$45.00	\$9,000.00
19.	300	CY	SCREENING MATERIAL	The installation of 2" thick minimum screening material over landscaping weed blocking fabric material	\$52.80	\$15,840.00	\$75.69	\$22,707.00	\$28.00	\$8,400.00
<b>SUM TOTAL BASE BID III (1 - 19)</b>					<b>\$609,885.00</b>		<b>\$603,522.20</b>		<b>\$458,870.00</b> Contractor's Price \$462,620.00	
<b>SUMTOTAL BASE BID I, BASE BID II and BASE BID III</b>					<b>\$5,453,463.00</b>		<b>\$7,263,668.20</b> Contractor's Price \$7,256,168.20		<b>\$5,557,980.00</b> Contractor's Price \$5,561,730.00	
AMENDMENT NO. 1 ACKNOWLEDGED:					YES		YES		YES	
BID BOND SUBMITTED					YES		YES		YES	

Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>					<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
<b>BASE BID I :</b>					<b>MARTINEZ BROS CONTRACTORS, LLC</b> <b>EL PASO, TX</b> <b>BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.</b> <b>EL PASO, TX</b> <b>BIDDER 5 OF 5</b>			
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
1.	5,800	CY	SIDEWALK	Sidewalk includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, HMAC patching, site restoration, cleanup, and proper disposal of all waste materials. Reference Section 6-12 of the Design Standards for Construction (DSC)	\$260.00	\$1,508,000.00	\$189.91	\$1,101,478.00		
2.	450	CY	6" STEM-WALL	6" Concrete stem-walls to include saw-cuts, excavation, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Technical Specifications Detail 3	\$648.00	\$291,600.00	\$245.44	\$110,448.00		
3.	3,200	CY	CURB STRUCTURE	Curb structure includes gutter if required, saw-cut, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching, backfill, cleanup, and proper disposal of waste material. Reference Sections 6-2 thru 6-6 of the DSC	\$179.50	\$574,400.00	\$147.38	\$471,616.00		
4.	15	CY	TXDOT PINNED CURB	TxDOT Pinned Curb includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching cleanup and proper disposal of all waste materials, Reference Technical Specifications Detail 5	\$580.00	\$8,700.00	\$183.57	\$2,753.55		
5.	1,750	CY	DRIVEWAY	Residential/Commercial Driveway includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching, cleanup and proper disposal of all waste materials. Reference Section 6-15 thru 6-18 of the DSC	\$240.00	\$420,000.00	\$173.73	\$304,027.50		

Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
					<b>MARTINEZ BROS CONTRACTORS, LLC</b> <b>EL PASO, TX</b> <b>BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.</b> <b>EL PASO, TX</b> <b>BIDDER 5 OF 5</b>				
<b>BASE BID I :</b>											
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
6.	875	CY	WHEELCHAIR RAMP	Wheelchair Ramp / Curb Cut includes saw-cuts, removal of existing structures, excavation, preparation and 95% compaction of subgrade, forming, concrete placement, ADA tile placement, compacted backfill, site restoration, HMAC patching, cleanup and proper disposal of all waste materials. Finished product must meet current TDLR and ADA requirements. Reference Section 0264 and Section 6-20 thru 6-30 of the DSC	\$617.00	\$539,875.00	\$210.14	\$183,872.50			
7.	15	CY	FLUME	Drainage Flume includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, HMAC patching cleanup and proper disposal of all waste materials. Reference Section 2-34 thru 2-36 of the DSC	\$300.00	\$4,500.00	\$381.88	\$5,728.20			
8.	62	PERCH	ROCKWALL	Rockwall includes excavation, preparation and compaction of foundation subgrade, reinforced concrete footing placement, wall construction, rockwall cap, site restorations, compacted backfill, cleanup and proper disposal of all waste materials. Perch paid on rock volume basis. Reference Section 4-3 of the DSC	\$140.00	\$8,680.00	\$243.15	\$15,075.30			
9.	7	PERCH	ROCKWALL RETAINING	Retaining Rockwall includes excavation, preparation and compaction of foundation subgrade, reinforced concrete footing placement, wall construction, rockwall cap, site restoration, compacted backfill, cleanup and proper disposal of all waste materials. Perch paid on rock volume basis. Reference Section 4-3 of the DSC	\$160.00	\$1,120.00	\$230.80	\$1,615.60			

Approved By:   
 Date: 2/4/16






# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016						BID NO: 2016-497		DEPARTMENT: CAPITAL IMPROVEMENT			
BID DATE: JANUARY 13, 2016											
					MARTINEZ BROS CONTRACTORS, LLC EL PASO, TX  BIDDER 4 OF 5		MIRADOR ENTERPRISES, INC.  EL PASO, TX  BIDDER 5 OF 5				
BASE BID I :											
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
10.	32	PERCH	RED ROCKWALL	Red Rockwall includes excavation, preparation and compaction of foundation subgrade, reinforced concrete footing placement, Franklin Red Rock wall construction, rockwall cap, site restoration, compacted backfill, cleanup and proper disposal of all waste materials. Perch paid on rock volume basis. Reference Section 4-3 of the DSC	\$180.00	\$5,760.00	\$249.06	\$7,969.92			
11.	159	SF	ROCKWALL RE-POINTING	Rockwall re-pointing: to include preparation and cleaning of existing joints, re-pointing with color matched Portland cement mortar (2,500 psi), site restoration, cleanup and proper disposal of all waste materials	\$5.00	\$795.00	\$6.99	\$1,111.41			
12.	100	SF	ROCK RIP-RAP	Rock Rip Rap includes excavation, preparation and compaction of subgrade, placement of reinforced concrete footing and rock rip rap elements, site restoration, compacted backfill, cleanup and proper disposal of waste materials. Measured on a Perch Basis. Reference Section 5-2 of the DSC	\$20.00	\$2,000.00	\$16.46	\$1,646.00			
13.	62	PERCH	ROCKWALL COLUMN	Rock wall columns includes excavation, preparation and compaction of foundation subgrade, placement of reinforced concrete footing and rock column elements, column cap, site restoration, compacted backfill, cleanup and proper disposal of waste materials. Measured on a Perch Basis. Reference Column Detail 13	\$260.00	\$16,120.00	\$228.77	\$14,183.74			
14.	40	CY	CONCRETE SLAB	Reinforced Concrete Slab includes saw-cuts, excavation, preparation and compaction of subgrade, forming, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Detail 14	\$302.50	\$12,100.00	\$218.31	\$8,732.40			


Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016							BID NO: 2016-497			
BID DATE: JANUARY 13, 2016							DEPARTMENT: CAPITAL IMPROVEMENT			
					MARTINEZ BROS CONTRACTORS, LLC EL PASO, TX  BIDDER 4 OF 5		MIRADOR ENTERPRISES, INC.  EL PASO, TX  BIDDER 5 OF 5			
BASE BID I :										
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
15.	45	CY	CONCRETE FOOTING	Footing for concrete slab includes saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming as required, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Detail 14	\$325.00	\$14,625.00	\$203.49	\$9,157.05		
16.	3	EACH	CONCRETE BUS PAD	Concrete bus pad w /approach concrete pad: to include saw-cuts, excavation, preparation and compaction of subgrade, reinforced concrete placement, compacted backfill, HMA paving, site restoration, cleanup and proper disposal of all waste materials. Reference Section 3-20 and 3-21 of the DSC	\$8,750.00	\$26,250.00	\$8,285.15	\$24,855.45		
17.	165	CY	CONCRETE PAVING	Concrete paving to include saw-cuts, excavation, preparation and compaction of subgrade, reinforced concrete placement, compacted backfill, restoration, cleanup and proper disposal of all waste materials. Reference Section 3 of the DSC and technical specifications figure 43	\$320.00	\$52,800.00	\$1,920.10	\$316,816.50		
18.	625	CY	MISC. CONCRETE	Miscellaneous Reinforced Concrete structure [drainage inlets and outlets, manholes, barrier walls] repair includes saw-cuts, excavation, preparation and compaction of subgrade, required forming, concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials	\$350.00	\$218,750.00	\$242.73	\$151,706.25		
19.	5	CY	CONCRETE CHANNEL LINING	Concrete channel lining: to include saw-cuts, excavation and/or fill up to 6 inches, preparation and compaction of subgrade, forming concrete placement, compacted backfill, restoration, cleanup and proper disposal of all waste materials. Reference Section 2-39 of the DSC	\$220.00	\$1,100.00	\$256.86	\$1,284.30		

Approved By:   
Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>					<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
<b>BASE BID I :</b>					<b>MARTINEZ BROS CONTRACTORS, LLC</b> <b>EL PASO, TX</b> <b>BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.</b> <b>EL PASO, TX</b> <b>BIDDER 5 OF 5</b>			
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
20.	5	CY	RETAINING CONCRETE WALL	8-inch Reinforced retaining concrete wall: includes saw-cuts, excavation, preparation and compaction of subgrade, required forming, reinforced concrete placement, compacted backfill, site restoration, cleanup and proper disposal of all waste materials. Reference Technical Specifications Detail 21	\$450.00	\$2,250.00	\$321.20	\$1,606.00		
21.	10	SY	EXPOSED AGGREGATE	Add Exposed aggregate texture finish using 3/4-inch max river rock	\$6.50	\$65.00	\$38.05	\$380.50		
22.	250	SY	COLOR TINT	Add concrete integrated color tint	\$12.00	\$3,000.00	\$15.26	\$3,815.00		
23.	260	SF	WROUGHT IRON GATE	Wrought iron gate, variable height: to include fabrication of wrought iron gate, posts and locking device, wheels when required, paint finish, concrete footing placement, site cleanup and proper disposal of all waste materials. Reference Section 4-4 of the DSC	\$12.00	\$3,120.00	\$33.67	\$8,754.20		
24.	5,450	SF	WROUGHT IRON FENCE	Wrought iron fencing, variable height: to include fabrication of wrought iron gate, end and line posts, paint finish, concrete footing placement, site cleanup and proper disposal of all waste materials. Reference Section 4-4 of the DSC	\$11.00	\$59,950.00	\$9.44	\$51,448.00		
25.	100	SF	CHAIN-LINK FENCE	Chain-link fence, variable height, to include all materials, chain-link fence fabric, fence posts, concrete footings, cleanup, site restoration and proper disposal of all waste materials. Item to be paid based on net area of installed metal fabric. Reference Section 4-1 and 4-2 of the DSC	\$8.00	\$800.00	\$4.95	\$495.00		

Approved By:

Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM


**BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016**
**BID DATE: JANUARY 13, 2016**
**BID NO: 2016-497**
**DEPARTMENT: CAPITAL IMPROVEMENT**

BASE BID I :					MARTINEZ BROS CONTRACTORS, LLC EL PASO, TX BIDDER 4 OF 5		MIRADOR ENTERPRISES, INC. EL PASO, TX BIDDER 5 OF 5			
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
26.	20	SF	CHAIN-LIN FENCE GATE	Chain-link fence gate, variable height, to include all materials, chain-link fence fabric, fence posts, concrete footings, wheels when required, cleanup, site restoration and proper disposal of all waste materials. Item to be paid based on net area of installed metal fabric. Reference Section 4-1 and 4-2 of the DSC	\$17.00	\$340.00	\$5.25	\$105.00		
27.	55	EACH	PARKING METER PIPE	Parking Meter Pipe includes saw-cuts/coring, excavation, concrete foundation; match existing surface finish, site restoration, cleanup, and proper disposal of all waste materials. Reference detail 25	\$165.00	\$9,075.00	\$580.81	\$31,944.55		
28.	25	EACH	PARKING METER PIPE WITH BASE PLATE MOUNT	Parking Meters Pipe Base Plate Mount includes installation of bolted plate, site restoration, cleanup, and proper disposal of all waste materials. Reference detail 25	\$165.00	\$4,125.00	\$705.45	\$17,636.25		
29.	525	CY	STAMPED COLORED CONCRETE	Stamped colored concrete; minimum of 3 stamp patterns, color match adjacent concrete or as directed by inspector, includes saw-cuts, excavation and/or fill up to 6 inches, preparation and 95% compaction of subgrade, reinforcement (if required), concrete placement, application of 2 coats of sealer, site restoration, cleanup and proper disposal of all waste materials. Reference Technical Specifications, Division III, Item 5326	\$350.00	\$183,750.00	\$321.41	\$168,740.25		
30.	1	EACH	6-INCH CONCRETE APRON	Installation of 6-inch reinforced concrete aprons in roadway around water valves, city monuments and manholes, includes proper elevation adjustment of valves, monument housings, manholes and concrete bells	\$267.00	\$267.00	\$1,576.67	\$1,576.67		

Approved By:

Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
<b>BASE BID 1:</b>					<b>MARTINEZ BROS CONTRACTORS, LLC EL PASO, TX BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC. EL PASO, TX BIDDER 5 OF 5</b>				
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
31.	20	EACH	MANHOLE ADJUSTMENT	Adjustment and level up of manhole to grade	\$225.00	\$4,500.00	\$560.87	\$11,217.40			
32.	180	EACH	BONNET BOX ADJUSTMENT	Adjustment and level up to grade of water meter, watervalue, city monument bonnets (concrete bell) for the sum of:	\$60.00	\$10,800.00	\$149.56	\$26,920.80			
33.	50	CY	TWO-SACK	Placement of two-sack backfill	\$100.00	\$5,000.00	\$112.17	\$5,608.50			
34.	6,050	CY	DEMOLITION	Demolition and removal: to include concrete, asphalt, dirt, subgrade, vegetation, debris with proper disposal. Reference Technical Specifications Division II Section 0210	\$10.00	\$60,500.00	\$93.11	\$563,315.50 Contractor's Price \$564,712.15			
35.	2,000	Lb	REINFORCING STEEL	Provide and install steel reinforcing deformed bars conforming to ASTM A 615, Grade 60, unless noted otherwise on the drawings and/or by request	\$1.50	\$3,000.00	\$0.84	\$1,680.00			
36.	60	DAY	TMA (24 hrs)	Special Traffic Control-Provide truck Mounted Attenuator when required	\$175.00	\$10,500.00	\$903.62	\$54,217.20			
37.	1,000	CY	AGGREGATE BASE COURSE	Base course composed of crushed aggregates placed and compacted on the prepared subgrade to required grades	\$30.00	\$30,000.00	\$33.22	\$33,220.00			

Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
					<b>MARTINEZ BROS CONTRACTORS, LLC</b> <b>EL PASO, TX</b> <b>BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.</b> <b>EL PASO, TX</b> <b>BIDDER 5 OF 5</b>				
<b>BASE BID I :</b>											
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
38.	1,000	CY	TOP SOIL BACKFILL	Placement of topsoil, Reference Technical Specifications Section 0220	\$10.00	\$10,000.00	\$15.75	\$15,750.00			
39.	500	CY	STRUCTURAL BACKFILL	Placement of structural material backfill to 95% compaction, Reference Technical Specifications Section 0220	\$10.00	\$5,000.00	\$17.62	\$8,810.00			
40.	20	EACH	TREE REMOVAL	The removal of tree various sizes ranging up to 18" caliper where required	\$150.00	\$3,000.00	\$989.62	\$19,792.40 Contractor's Price \$19,792.00			
41.	150,000	SF	WIRE MESH REINFORCEMENT	Provide and install Prefabricated 6" X 6", Welded Wire Fabric	\$0.50	\$75,000.00	\$0.52	\$78,000.00			
42.	400	Hr	UTILITY LINE REPAIR	Provide for all labor, superintendence, equipment, supplies etc. to repair damaged water or gas lines and meters as required by the project due to no fault of the contractor	\$100.00	\$40,000.00	\$185.02	\$74,008.00			
<b>SUM TOTAL BASE BID I (1 - 42)</b>					<b>\$4,231,217.00</b>		<b>\$3,913,118.89</b> Contractor's Price \$3,914,515.54				

Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
<b>BASE BID II :</b>					<b>MARTINEZ BROS CONTRACTORS, LLC EL PASO, TX  BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.  EL PASO, TX  BIDDER 5 OF 5</b>				
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
1.	570	LF	3" PVC CONDUIT-TRENCHING	PVC conduit 3-inch installed by trenching to include saw cut, excavation, backfill, compaction, pavement removal & patching, and disposal of waste material, Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes: of the Technical Specifications	\$22.50	\$12,825.00	\$24.53	\$13,982.10			
2.	10,100	LF	2" PVC CONDUIT-TRENCHING	PVC conduit 2-inch installed by trenching: to include, sawcut, excavation, backfill, compaction, pavement removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$18.54	\$187,254.00	\$19.36	\$195,536.00			
3.	650	LF	3" PVC CONDUIT-BORING	PVC conduit 3-inch installed by directional boring: to include, boring, excavation, backfill, compaction, pavement removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundation, and Ground Boxes" of the Technical Specifications.	\$41.20	\$26,780.00	\$40.44	\$26,286.00			
4.	14,300	LF	2" PVC CONDUIT-BORING	PVC conduit 2-inch installed by directional boring: to include, boring, excavation, backfill, compaction, pavement removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$37.08	\$530,244.00	\$36.15	\$516,945.00			

Approved By: \_\_\_\_\_  
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
<b>BASE BID II :</b>					<b>MARTINEZ BROS CONTRACTORS, LLC EL PASO, TX BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC. EL PASO, TX BIDDER 5 OF 5</b>				
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
5.	150	EACH	GROUND BOX TYPE A	Ground Box Type A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, concrete apron, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$1,545.00	\$231,750.00	\$1,306.80	\$196,020.00			
6.	25	EACH	GROUND BOX TYPE C	Ground Box Type C installed in place: to include, excavation, backfill, compaction, concrete removal & patching, concrete apron, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$1,800.00	\$45,000.00	\$1,560.57	\$39,014.25			
7.	45	EACH	FOUNDATION TRAFFIC SIGNAL TYPE 24A	Foundation, Traffic Signal Type 24A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$1,957.00	\$88,065.00	\$1,000.39	\$45,017.55			
8.	115	EACH	FOUNDATION TRAFFIC SIGNAL TYPE 30A	Foundation, Traffic Signal Type 30A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$4,387.80	\$504,597.00	\$1,160.29	\$133,433.35			

Approved By:   
 Date: 2/4/16





# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
					<b>MARTINEZ BROS CONTRACTORS, LLC</b> <b>EL PASO, TX</b> <b>BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.</b> <b>EL PASO, TX</b> <b>BIDDER 5 OF 5</b>				
<b>BASE BID II :</b>											
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
9.	2	EACH	FOUNDATION TRAFFIC SIGNAL TYPE 36A	Foundation, Traffic Signal Type 36A installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations and Ground Boxes" of the Technical Specifications	\$5,407.50	\$10,815.00	\$1,471.81	\$2,943.62			
10.	2	EACH	FOUNDATION TRAFFIC CONTROLLER	Foundation, Traffic Controller installed in place: to include, excavation, backfill, compaction, concrete removal & patching, and disposal of waste material. Reference Division VI, "Installation of Conduit, Loops, Foundations, and Ground Boxes" of the Technical Specifications	\$8,085.50	\$16,171.00	\$299.54	\$599.08			
11.	40	EACH	RECTANGULAR CONCRETE APRON	Installation of rectangular reinforced concrete aprons around Ground Boxes. To include proper elevation adjustment of ground boxes. Reference Technical of the Technical Specifications General Requirement for All Electrical Work Figure 34	\$978.50	\$39,140.00	\$378.10	\$15,124.00			
<b>SUM TOTAL BASE BID II (1 - 11)</b>					<b>\$1,692,641.00</b>		<b>\$1,184,900.95</b>				

Approved By:   
 Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>					
					<b>MARTINEZ BROS CONTRACTORS, LLC</b> <b>EL PASO, TX</b> <b>BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.</b> <b>EL PASO, TX</b> <b>BIDDER 5 OF 5</b>				
<b>BASE BID III :</b>											
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
1.	300	EACH	4" CALIPER TREE	The installation of minimum 4" caliper tree where required	\$850.00	\$255,000.00	\$814.59	\$244,377.00			
2.	300	EACH	3" CALIPER TREE	The installation of minimum 3" caliper tree where required	\$450.00	\$135,000.00	\$506.03	\$151,809.00			
3.	300	EACH	2" CALIPER TREE	The installation of minimum 2" caliper tree where required	\$330.00	\$99,000.00	\$333.24	\$99,972.00			
4.	400	EACH	5 GAL. SHRUBS	The installation of minimum 5 gallon container shrub where required	\$40.00	\$16,000.00	\$31.46	\$12,584.00			
5.	400	EACH	1 GAL. SHRUBS	The installation of minimum one (1) gallon container groundcover where required	\$20.00	\$8,000.00	\$16.27	\$6,508.00			
6.	40	EACH	BACKFLOW PREVENTER	The installation of 2-inch double check backflow preventer where required	\$1,458.00	\$58,320.00	\$1,049.09	\$41,963.60			
7.	20	EACH	WATER PRESSURE REGULATOR	The installation of water pressure regulator bronze body or inline pressure regulator 30 PSI where required	\$904.00	\$18,080.00	\$1,357.65	\$27,153.00			
8.	20	EACH	TBOS	The installation of TBOS battery operated system where required	\$288.00	\$5,760.00	\$316.27	\$6,325.40			

Approved By: \_\_\_\_\_

Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016						BID NO: 2016-497					
BID DATE: JANUARY 13, 2016						DEPARTMENT: CAPITAL IMPROVEMENT					
BASE BID III :					<b>MARTINEZ BROS CONTRACTORS, LLC</b> EL PASO, TX BIDDER 4 OF 5		<b>MIRADOR ENTERPRISES, INC.</b> EL PASO, TX BIDDER 5 OF 5				
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	
9.	20	EACH	BOX FOR BACKFLOW	The installation of reinforced concrete box for backflow 17 inches by 30 inches with screw down steel checker lid, where required	\$952.00	\$19,040.00	\$254.56	\$5,091.20			
10.	20	EACH	REMOTE VALVE	The installation of electric remote valve with latching solenoid where required	\$274.20	\$5,484.00	\$223.70	\$4,474.00			
11.	3,600	LF	¼ " DISTRIBUTION TUBING	The installation of ¼ inch distribution tubing where required	\$0.14	\$504.00	\$0.52	\$1,872.00			
12.	1,200	EACH	DRIP EMITTERS	The installation of drip emitters, where required	\$0.50	\$600.00	\$1.78	\$2,136.00			
13.	9,000	LF	SCHEDULE 40 PIPE	The installation of ¾ inch PVC pipe schedule 40 (includes excavation, backfill, all fitting) where required	\$1.08	\$9,720.00	\$1.43	\$12,870.00			
14.	20	EACH	Y-STRAINER	The installation of Y-Strainer, where required	\$74.00	\$1,480.00	\$308.56	\$6,171.20			
15.	9,000	LF	DRIPLINE	The installation of ¾ inch PLD dripline tubing (includes excavation, backfill, all fittings) where required	\$0.80	\$7,200.00	\$6.17	\$55,530.00			

Approved By:

Date: 2/4/16



# CITY OF EL PASO BID TABULATION FORM



<b>BID TITLE: CITYWIDE MAINTENANCE OF PARKWAY STRUCTURES 2015-2016</b> <b>BID DATE: JANUARY 13, 2016</b>						<b>BID NO: 2016-497</b> <b>DEPARTMENT: CAPITAL IMPROVEMENT</b>				
<b>BASE BID III :</b>					<b>MARTINEZ BROS CONTRACTORS, LLC</b> <b>EL PASO, TX</b> <b>BIDDER 4 OF 5</b>		<b>MIRADOR ENTERPRISES, INC.</b> <b>EL PASO, TX</b> <b>BIDDER 5 OF 5</b>			
ITEM #	EST. QTY	UNIT	SHORT DESCRIPTION	BRIEF DESCRIPTION OF ITEM	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)	UNIT PRICE	TOTAL AMOUNT (Qty x Unit Price)
16.	400	CY	2" ROCK	The installation of 2" minimum size franklin red rock over landscaping weed blocking fabric material	\$89.50	\$35,800.00	\$247.91	\$99,164.00 Contractor's Price \$74,373.00		
17.	300	CY	4" ROCK	The installation of 4" minimum size franklin red rock over landscaping weed blocking fabric material	\$81.37	\$24,411.00	\$169.84	\$50,952.00		
18.	200	CY	6" + ROCK	The installation of 6" minimum size river rock over landscaping weed blocking fabric material	\$255.72	\$51,144.00	\$258.71	\$51,742.00		
19.	300	CY	SCREENING MATERIAL	The installation of 2" thick minimum screening material over landscaping weed blocking fabric material	\$75.33	\$22,599.00	\$103.81	\$31,143.00		
<b>SUM TOTAL BASE BID III (1 - 19)</b>					<b>\$773,142.00</b>		<b>\$911,837.40</b> Contractor's Price \$887,046.40			
<b>SUMTOTAL BASE BID I, BASE BID II and BASE BID III</b>					<b>\$6,697,000.00</b>		<b>\$6,009,857.24</b> Contractor's Price \$5,986,046.40			
<b>AMENDMENT NO. 1 ACKNOWLEDGED:</b>					YES		YES			
<b>BID BOND SUBMITTED</b>					YES		YES			

Approved By:

Date: